


NORMAN UTILITIES AUTHORITY
 CITY OF NORMAN
 CLEVELAND COUNTY, OKLAHOMA

DATE: January 29, 2020
 CHANGE ORDER NO.: One (1)
 CONTRACT NO.: Contract K-1819-125
 PROJECT: Robinson Street Waterline Replacement, Phase II
 CONTRACTOR: Central Contracting Services, Inc.
17301 S. Sunnyslane Ave
Norman, OK 73071

	<u>Contract Time</u>		<u>Contract Amount</u>
ORIGINAL:	<u>240</u>	calendar days	<u>\$2,845,591.00</u>
PREVIOUS CHANGE ORDERS:	<u>0</u>	calendar days	<u>\$0.00</u>
THIS CHANGE ORDER:	<u>90</u>	calendar days	<u>\$193,130.00</u>
REVISED AMOUNT:	<u>330</u>	calendar days	<u>\$3,038,721.00</u>
ORIGINAL START DATE:	<u>April 15, 2019</u>		
ORIGINAL COMPLETION DATE:	<u>December 11, 2019</u>		
PREVIOUS COMPLETION DATE:	<u>December 11, 2019</u>		
NEW COMPLETION DATE:	<u>March 10, 2020</u>		

DESCRIPTION:	\$ Increase	\$ Decrease
Install approximately 520 feet of new waterline (WL) to replace existing WL and valves located adjacent to new On-Cue Convenience Store located NW of State Highway 9 and Classen Boulevard as detailed on Attachment 1. Upsize approximately 360 feet of existing 24-inch WL to 30-inch WL. Increase contract time by ninety (90) calendar days to complete the additional work.	193,130.00	0.00

SUBMITTED BY
 CONTRACTOR: 
 Central Contracting Services, Inc.

Date: 01-29-20


RECOMMENDED BY
 ENGINEER: 
 Mark Daniels, P.E., Utilities Engineer

Date: _____

ACCEPTED BY
 NORMAN UTILITIES AUTHORITY: _____
 City Attorney

Date: _____

ACCEPTED BY
 NORMAN UTILITIES AUTHORITY: _____
 Breaa Clark, Chairperson

Date: _____

Change Order No. 1

Contract K-1819-125

Attachment 1

Item 1: Install approximately 520 feet of new waterline (WL) to replace existing WL and valves located adjacent to new On-Cue Convenience Store located NW of State Highway 9 and Classen Boulevard. Upsize approximately 360 feet of existing 24-inch WL to 30-inch WL. Do not replace existing driveway and sidewalk damaged by WL construction as On-Cue Convenience Store will perform this work. Increase contract time by ninety (90) calendar days to complete the additional work.

This change order to be funded under Classen-Flood Waterline, Project WA0338, 31996683-46101.

Bid Item	Description	Unit	Quantity	Unit Price	Total Price
4	Open Trench 16" PVC Pipe	LF	120	\$53.00	\$6,360.00
6	Open Trench 30" PVC Pipe	LF	400	\$250.00	\$100,000.00
12	16" Butterfly Valve with Box	EA	1	\$3,625.00	\$3,625.00
14	30" Butterfly Valve with Box	EA	2	\$13,865.00	\$27,730.00
19	16" Epoxy Coated MJ 45 Degree Bend	EA	2	\$1,765.00	\$3,530.00
24	30" Epoxy Coated MJ 45 Degree Bend	EA	4	\$4,445.00	\$17,780.00
32	30" x 30" MJ Tee	EA	1	\$6,995.00	\$6,995.00
36	30" x 16" MJ Reducer	EA	1	\$2,990.00	\$2,990.00
37	30" x 24" MJ Reducer	EA	1	\$3,160.00	\$3,160.00
48	Connection to Existing 16" Water Line	EA	1	\$1,000.00	\$1,000.00
49	Connection to Existing 24" Water Line	EA	1	\$2,500.00	\$2,500.00
50	Connection to Existing 30" Water Line	EA	1	\$3,500.00	\$3,500.00
73	Mobilization & Insurance (5%)	LS	1	\$8,960.00	\$8,960.00
NEW	Pressure Testing	LS	1	\$2,500.00	\$2,500.00
NEW	Disinfection	LS	1	\$2,500.00	\$2,500.00
				Net Change to Contract Price =	\$193,130.00