

**MATERIALS ESTIMATE FOR SUMMIT LAKES ADDITION SECTION 11
DEFERRED PAVING QUANTITIES FOR 24TH AVENUE SE
NORMAN, OKLAHOMA**

July 25, 2018

Paving

<u>Item</u>	<u>Quan.</u>	<u>Unit</u>	<u>Unit Cost</u>	<u>Total</u>
8" Curb and Gutter	504	L.F.	\$ 20.00	\$ 10,080.00
2" Type "S5" Asphalt Concrete	1953	S.Y.	\$ 10.85	\$ 21,190.05
4" Type "S3" Asphalt Concrete	1953	S.Y.	\$ 17.00	\$ 33,201.00
6" Modified Subgrade (14% CKD)	2085	S.Y.	\$ 7.55	\$ 15,741.75
3" Type "S3" Asphalt	2085	S.Y.	\$ 14.15	\$ 29,502.75
5' Concrete Sidewalk	560	L.F.	\$ 19.00	\$ 10,640.00
Excavation & Grading	1	L.S.	\$ 2,000.00	\$ 2,000.00
Erosion Control	1	L.S.	\$ 1,000.00	\$ 1,000.00
Traffic Control	1	L.S.	\$ 1,000.00	\$ 1,000.00

Subtotal \$ **124,355.55**

TOTAL FOR DEFERRED CONSTRUCTION COST **\$ 124,355.55**

OK
E. M. M.
7-26-18