



REQUEST FOR PROPOSALS:
THE CENTRAL OKLAHOMA ALLIANCE OF
GOVERNMENT AGENCIES 2019 (COAGA 2019)

REGIONAL DIGITAL ORTHOPHOTO
IMAGES AND ASSOCIATED DATA

RFP # 2019-01

PROPOSALS MUST BE RECEIVED
NO LATER THAN 2:00 P.M. CST
DECEMBER 7, 2018

FOR INFORMATION REGARDING
THIS PROPOSAL CONTACT:

John Sharp
(405) 234-2264
jmsharp@acogok.org

4205 N. Lincoln Blvd. | Oklahoma City, OK 73105
405.234.2264 | Fax: 234.2200 | acogok.org

ASSOCIATION OF
CENTRAL OKLAHOMA
GOVERNMENTS

TABLE OF CONTENTS

Section 1: Purpose	2
Section 2: Award	2
Section 3: RFP Submittal.....	2
Section 4: Insurance or Other Required Documents (if required)	3
Section 5: Terms & Conditions	3
Section 6: RFP Status	5
Section 7: Exceptions, Omissions, and Alternatives	6
Section 8: Proposal Format and Contents	6
Section 9: Specifications	8
Section 10: Cost Proposal Forms	13
Appendix A: Project Overview Map.....	15
Appendix B: Project Deliverables	16
Appendix C: City of Edmond.....	18
Appendix D: City of Del City.....	37
Appendix E: City of Midwest City	38
Appendix F: City of Moore	41
Appendix G: City of Norman.....	42
Appendix H: Canadian County (ACOG)	76
Appendix I: Forms.....	77
Appendix J: Metadata Requirements	78

Request for Proposals for Regional Digital Orthophoto Images and Associated Data

Date: November 21, 2018

The Request for Proposal is part of a competitive procurement process which will facilitate a fair opportunity for qualified firms to offer their plans and services for consideration. The process of competitive negotiation being used should not be confused with competitive sealed bidding where goods and services can be precisely described and price is generally the determination factor. The competitive Request for Proposal will provide the participating agencies of Central Oklahoma Alliance of Government Agencies 2019 (COAGA 2019) the flexibility to negotiate with firms to arrive at a mutually agreeable relationship, where price alone is not the major determination factor; however, price will be a priority factor.

Section 1: Purpose

The COAGA 2019 seeks proposals from qualified and experienced firms to collect and produce digital orthophoto images; and separately collect, detect changes and update the participating agencies planimetric and topographic data for the project areas defined in the RFP. The goal is to have a complete up-to-date accurate digital ortho data set for the entire project area as well as updated planimetric and drainage-enforced contour data sets for the specified municipal areas. Each participating agency may negotiate a separate agreement.

Section 2: Award

- 2.1 The participating agencies of COAGA 2019 reserve the right to award this contract, not necessarily to the firm with the lowest cost, but to the firm that best meets the requirements and needs of the participating agencies of COAGA 2019 as determined by the participating agencies of COAGA 2019.
- 2.2 Upon submission of the responses to this RFP, the participating agencies of COAGA 2019 will evaluate and score the responses of the firms. The participating agencies of COAGA 2019 may conduct interviews with the finalists. The final evaluation and selection of a contractor will be made by the participating agencies of COAGA 2019 and submitted to each agency for approval.

Section 3: RFP Submittal

All proposals must be mailed or hand delivered to ACOG before the FINAL CLOSING DATE AND HOUR ON December 7, 2014 by 2:00 pm CST. Proposals submitted AFTER the time set for receipt of proposals WILL NOT BE CONSIDERED. One (1) unbound original, eight (8) copies, and an electronic copy of the response shall arrive no later than the closing date and time to the following location:

ACOG
4205 N. Lincoln Blvd.
Oklahoma City, OK 73105
Phone (405) 234-2264
e-mail: jmsharp@acogok.org

- 3.1. Mailed in proposals or proposals hand delivered directly to ACOG are to be received in sealed envelopes with the name of the respondent, RFP number, project name (Request for Proposal for Professional Services for Regional Digital Orthophoto Images and Associated Data) and closing date plainly stated on the face of the sealed envelope. All

costs associated directly or indirectly with responding to this RFP including, but not limited to, preparation of a response, any oral presentation or meetings required to supplement and/or clarify a proposal, which may be required by the participating agencies of COAGA 2019, shall be the sole responsibility of and shall be borne by the respondent.

- 3.2. Facsimile proposals will not be accepted.
- 3.3. The proposals shall be in the specific format prescribed herein. Proposals may contain promotional or display materials pertinent to displaying the quality of print publication to be expected, and all material shall pertain to the requirements set forth in this document. Proposals shall be straightforward, providing a concise description of the respondent's ability to meet the requirements of this RFP. Emphasis should be on completeness and clarity of intent. Submitted proposals are subject to release under the Oklahoma Open Records Act.
- 3.4. Failure to provide required data to allow for evaluation, failure to complete the RFP form(s) or failure to follow all directions within this RFP may be grounds for rejecting the RFP.
- 3.5. Inquiries: Inquiries should be submitted in writing by email:

ACOG
Phone (405) 234-2264
e-mail: jmsharp@acogok.org
Attn: John Sharp

- 3.6. Responses to written questions will be made by way of addendum sent to all vendors who are registered with ACOG as having received a Request for Proposal. Only replies by formal written addenda (amendments) shall be binding.

3.7. Schedule of Events

Proposal Issued	11/21/2018
Inquiries Due	11/30/2018 - 5:00pm CST
Proposal(s) Due	12/7/2018 - 2:00pm CST
Evaluation Completed	1/2/2019 - Approximate
Anticipated Date of Award	1/23/2019 - Approximate

Section 4: Insurance or Other Required Documents (if required)

- 4.1 Permits: The contractor shall procure all necessary permits and pay for same, and shall obtain all official licenses for the work necessary. The contractor shall be responsible for all violations of the law for any cause in connection with the work caused by the contractor.
- 4.2 Insurance: The contractor will be responsible for all required insurance of property owned or services provided by the contractor.
- 4.3 Comprehensive General and/or Public Liability with a minimum of \$1,000,000.00 Bodily injury, and Property damage, combined single limit.
- 4.4 Automobile Insurance with a minimum \$1,000,000.00 per accident Bodily injury and Property damage, combined single limit.

Section 5: Terms & Conditions

- 5.1 Terms and conditions below will govern the submission and evaluation of proposals and the award. Respondents are requested to carefully review the following (5.2-5.14):

- 5.2 Award Status: After the award of the winning bid each agency of COAGA 2019 will negotiate and execute a legal and binding contract.
- 5.3 Contract Format/Requirements: The resulting acceptance will incorporate this Request for Proposal. All additional agreement(s) and stipulations and the results of any final negotiations will be incorporated. Due to the nature of this request and number of participating agencies, this may result in multiple contracts.
- 5.4 Contract Modification: All modifications and/or changes to the contract must be agreed to in writing by both parties prior to executing any change.
- 5.5 Contract Termination: The participating agencies of COAGA 2019 may terminate any resulting contract for cause by providing a Show Cause Letter to the contractor citing the instances of noncompliance with the contract. The terms of the contract between the contractor and agency shall control the terms.
- 5.6 If the noncompliance is not cured within 30 days, the participating agencies of COAGA 2019 may terminate the contract.
- 5.7 The participating agencies of COAGA 2019 reserve the right to terminate the contract for convenience upon sixty (60) day written notice.
- 5.8 Conflict of Interest: In the event there is a potential or actual conflict of interest, the respondent(s) shall provide full disclosure to the participating agencies of COAGA 2019. The participating agencies of COAGA 2019 shall determine if the conflict, whether potential or actual, is material. COAGA 2019 has the right to determine if there is a conflict and reserves the right to disqualify the respondent if the conflict is material.
- 5.9 Contractor Liability: The contractor shall hold the participating agencies of COAGA 2019 harmless and shall be liable in the event of injury to agency personnel or damage or loss of their property caused by the contractor's equipment, personnel, supplies or material furnished. The participating agencies of COAGA 2019 will not be liable for loss or damage caused by fires, lightning, sprinkler leakage, earthquake, severe weather, smoke and smudge, aircraft or motor vehicle damage, strikes, riots and civil disturbance or collapse of building or structures, etc. The participating agencies of COAGA 2019 and its personnel shall not be liable for any loss of or damage to contractor property unless due to their fault or negligence.
- 5.10 Liens: The contractor shall keep the participating agencies of COAGA 2019 free and clear from all liens asserted by any person or firm for any reason arising out of the furnishing of services or materials by or to the contractor.
- 5.11 Indemnification: The contractor shall indemnify and hold the participating agencies of COAGA 2019 harmless from all claims and related expenses arising out of the contractor's performance or failure of performance under the resulting contract.
- 5.12 Disclosure of Proposal Content: All proposals become a matter of public record once opened. By submitting a proposal, a respondent specifically assumes any and all risks and liabilities associated with the information contained in the proposal and the release of that information. If a respondent does not desire proprietary information in the proposal to be disclosed, each page must be identified and marked proprietary at time of submittal. The participating agencies of COAGA 2019 will, to the extent allowed by law, endeavor to protect such information from disclosure. If the respondent fails to identify proprietary information, he agrees that by submission of his proposal those sections shall be deemed non-proprietary and available upon public request.
- 5.13 Choice of Law and Venue: The resulting contract shall be construed under the laws of the State of Oklahoma and venue in any action and/or litigation commenced to enforce the

contract shall be instituted in the appropriate courts in Cleveland or Oklahoma County in the State of Oklahoma.

- 5.14 Federal, State and Local Laws and Regulations: The contractor will comply with all laws and regulations including taxes, licenses and permits.

Section 6: RFP Status

6.1. COAGA 2019 Rights:

- The participating agencies of COAGA 2019 reserve the right to determine whether a proposal is responsive and has the ability and resources to perform the contract in full and comply with the specifications.
- The participating agencies of COAGA 2019 reserve the right to reject proposals that incorporate counter proposals and conditions in the form of vendor's pre-printed clauses.
- The participating agencies of COAGA 2019 reserve the right to accept or reject all or part of any proposal, waive informalities, minor irregularities or substitute items as desired if deemed in the best interest of the participating agencies of COAGA 2019, therefore selecting the optimum proposal or issue a new RFP.
- The participating agencies of COAGA 2019 reserve the right to reject proposals when procedures stated within are not followed.
- Should the proposal include any work of a subcontract nature, the participating agencies of COAGA 2019 reserve the right to approve or disapprove the engagement or use of the subcontractor as it relates to services provided to the participating agencies of COAGA 2019 as described in this RFP. COAGA 2019 reserves the right to reject any subcontractor.
- The participating agencies of COAGA 2019 reserve the right to negotiate separately if deemed necessary.

- 6.2. Effective Period: Proposals submitted must remain in effect for a period of ninety (90) days after the closing date. An award will be signed and issued within that time or at a negotiated later date.

- 6.3. Withdrawal of Proposals: Proposals may be withdrawn at any time prior to the closing date; however, the participating agencies of COAGA 2019 reserve the right to withdraw respondents(s) from future RFPs who have withdrawn a proposal after the closing date and prior to the effective period of the RFP without the participating agencies of COAGA 2019's approval.

- 6.4. Changes: It shall be the respondent's responsibility to bring to the attention of the participating agencies of COAGA 2019 any discrepancies in, omissions from or errors in the documents, or enhancements which would be in the best interest of the participating agencies of COAGA 2019, or if they are in doubt as to the meaning of any part of the RFP.

- 6.5. Examinations: Before submitting a proposal, contractor shall thoroughly examine the RFP as well as location and otherwise be fully informed as to all existing conditions and limitations.

- 6.6. Modifications of RFP: Oral modifications will not be considered. Any respondent may modify his/her proposal in writing prior to the date and time of RFP closing. Only modifications received in sealed envelopes with the RFP number, closing date, and the project name clearly marked on the outside will be accepted. Written confirmation of the modification must be received under the same signature as the prior submitted proposal. All modifications are to be clearly numbered and dated as to determine the final one.

- 6.7. Sales Tax Exemption: All proposals must be submitted exclusive of Federal Excise Tax and Oklahoma State Tax. The participating agencies of COAGA 2019 are exempt from Federal Excise Tax and Oklahoma State Tax. When proof of a tax exemption status is required, a notation should be made in the proposal and an Exemption Letter shall be furnished.
- 6.8. Clarification: The participating agencies of COAGA 2019 reserve the right to request clarification of information submitted and to request additional information from any or all of the respondents.

Section 7: Exceptions, Omissions, and Alternatives

- 7.1 Exceptions: If any exceptions are taken to any portion of the RFP, the respondent must clearly indicate the exceptions taken and include a full explanation as a separate attachment to the proposal. The failure to identify exceptions or proposed changes with a full explanation will constitute acceptance by the Respondent of the RFP as proposed by the participating agencies of COAGA 2019.
- 7.2 Omissions: Add descriptions of any possible omissions from the RFP.
- 7.3 Alternatives: Provide descriptions of any alternative or optional functionality that the respondent deems advantageous or beneficial to the participating agencies of COAGA 2019.

Section 8: Proposal Format and Contents

- 8.1 Contents: All proposals shall include the following information at a minimum:
- Cover Letter
 - Project Overview
 - Project Approach
 - Management Proposal
 - Exceptions to the RFP
 - Additional Pertinent Information
 - Fee Proposal
- 8.2 Cover Letter: The Cover Letter shall identify the persons in the respondent's organization who will respond to questions or additional requests by the participating members of COAGA 2019
- 8.3 Project Overview: The Project Overview should highlight the major features of the Respondent's company and proposal. It should also include information about the firm and any proposed subcontractors. A summary of the project approach should be presented in this section.
- 8.4 Project Approach: This section is intended to be the core of the proposal and should demonstrate the respondent's knowledge of the data conversion/update process. This section shall clearly show the respondent understands the scope of work (9.2) as presented in the Technical Specifications (9.3). A detailed explanation of the process methodology to be used on this project shall be thoroughly defined.
- Respondents shall develop and present in their proposals a technical plan of operations for providing aerial photography for use in the production of digital orthophotography and the compilation/update of the geodatabase as defined in the appendices. The respondent's proposed plan shall clearly demonstrate a complete understanding of the project. The respondent shall use accepted map compilation and conversion procedures and equipment to achieve the levels of accuracy, detail, and quality required by the RFP.

- The technical plan of operations shall detail the methodology, equipment, and proposed techniques to be used to capture the aerial photography and the production of digital orthoimagery. The plan shall detail the sequence of operations to be performed for the entire project, emphasizing steps taken to ensure meeting quality and accuracy standards. It shall also clearly indicate any additional information pertinent to this project.
- All proposed equipment to be used by the respondent shall be specified. The contractor is required to deliver products in a format as stated in the specifications and appendices in this RFP. The contractor shall be able to deliver Digital Orthoimagery as uncompressed TIFF formatted file associated with a TIFF World header file (.TFW), MrSID and JP2000.
- All aerial photography shall be accomplished with such equipment as to afford photographs meeting all precision requirements for aerotriangulation and map compilation conforming to National Map Accuracy Standards. The respondent's hardware and software shall have the capability to digitize; perform graphic editing; use automated techniques to match edges of automated map sheets (edge matching); create topological relationships of the digitized points, lines, and polygons automatically; provide for the automatic creation and storage of attributes for point, line, and polygon features; and also have the capabilities for error analysis and DVD output.

8.5 Management Proposal: This section should include available resources for completing this project, as well as an anticipated project schedule. Include relevant experience of the company and project team. This should include, at a minimum, three comparable customer references. The same information and relevant experience should be included for subcontractors of the respondent.

The Management Proposal shall include at a minimum the respondent's description of how they propose to satisfy the following requirements (8.6-8.13):

- 8.6 Coordination with the participating members of COAGA 2019: Communication between the participating members of COAGA 2019 and the contractor is critical. A designated staff person from each participating member of COAGA 2019 will be responsible for the coordination of each agency with the vendor for the duration of the contract. The respondents shall indicate how they will arrange and monitor communication and document ensuing decisions and resolutions. A description shall be provided of the proposed questions and resolution procedures to be used for this project
- 8.7 Overview of Proposed Schedule: Indicate the schedule for completing the deliverables indicated in the RFP. The COAGA 2019 reserves the right to negotiate a different schedule from that proposed.
- 8.8 Project Tracking and Reporting: The Contractor shall maintain procedures throughout the project for tracking and reporting progress in the data conversion and update process.
- 8.9 Staffing: The respondent will identify the essential staff resources assigned to this project and will provide their resumes. Essential staff includes at a minimum the project manager and the quality assurance specialist assigned to this project. The respondent shall indicate the role of these individuals in this project and what percent of their overall time this project shall represent. The participating members of COAGA 2019 reserve the right to approve any reassignment of these essential staff resources.
- 8.10 Resolution of Source Anomalies: It is anticipated that inconsistencies and anomalies between source materials and specifications will occur. It shall be the responsibility of the contractor to bring such issues to the attention of each of the participating designated project managers. The contractor and the participating members of COAGA 2019 shall

work together to resolve issues and problems that arise. Techniques for communicating such problems to the project manager for each participating agency shall be addressed in the respondent's proposal. Procedures and guidelines for the resolution of problems shall be included in the proposal, with procedures being formalized during the project initiation phase and reviewed and modified as necessary during the project.

- 8.11 Exceptions to the RFP: List any exceptions to the RFP. Elaborate on the reasons for the exceptions and proposed alternatives.
- 8.12 Additional Pertinent Information: Add descriptions of any possible omissions from the RFP.
- 8.13 Fee Proposal: The COAGA 2019 is seeking firm fixed prices for the performance and delivery of regional digital orthoimagery and updates to planimetric and topographic data in specific areas. Refer to the Appendices B-I for detailed information on deliverables. Section 9 of the RFP contains specifications that apply to all data collected as a part of this project. Forms that must be completed include the cost worksheet in Section 10 of the RFP and the Appendix I: Forms.

Section 9: Specifications

- 9.1 Project Background: The RFP is being coordinated by the Association of Central Oklahoma Governments (ACOG) to support the data acquisition needs related to digital orthoimagery, planimetric mapping, and topographic mapping of its member governments and agencies participating in the COAGA 2019. The total area of the base project is approximately 1,351.85 square miles. All of the participating governments will be updating their digital orthoimagery base map. Appendix B contains the overall project map for deliverables needed for the orthoimagery portion of this project. Appendix A provides a summary map of the project area as well as a list of the potential participating agencies. Appendix J contains the standards for the metadata that will be collected as a part of this project.

The following central Oklahoma municipalities are participating in the project: Edmond, Del City, Midwest City, Moore, Norman and Canadian County (via ACOG). Special attention needs to be paid to the coordinate system and datum which the mapping products will be delivered in as the divide between Oklahoma State Plane North and Oklahoma State Plane South occurs in the project area. All of the products will be delivered in a version of the State Plane Coordinate System; however, each jurisdiction will give the specifics of their projection system within the Appendix which details their individual requirements. Different jurisdictions use different adjustments to the datum. These adjustments include both NAD83 and HARN. It is the responsibility of the contractor to convert the final deliverables to the coordinate system used by the jurisdiction taking final possession of the products in a manner that will meet all map accuracy requirements. The orthoimagery delivered to each jurisdiction will match the coordinate system and datum of their base map. See Appendices C - H for overview maps of the coordinate systems and datum used by the participating entities. A brief synopsis of each of the participating communities including the appendix in which you will find a more detailed description of the scope of work required by each community follows.

Appendix C details the requirements of the **City of Edmond**. The City of Edmond is situated in the northern part of the project area. Edmond's project area is approximately 127 square miles with a population of approximately 92,000. The aerials were last updated in 2018.

Appendix D describes the requirements of the **City of Del City**. Del City has a population of approximately 21,332 and covers an extent of 7.52 square miles. The aerials were last updated in 2017.

Appendix E describes the **City of Midwest City**. Midwest City has a population of 55,000 and covers an extent of 26.6 square miles (project 42.43 sq. mi.). Midwest City last updated its aerial data in 2017.

Appendix F describes the **City of Moore**. Moore has a population of 52,361 and covers an extent of 21.9 square miles. Moore last updated its aerial data in 2017.

Appendix G describes the **City of Norman**. Norman has a population of approximately 122,000 and covers an extent of 256 square miles. Norman last updated its aerial data in 2017.

Appendix H describes the **County of Canadian County**. Canadian County has a population of 139,926 and covers an extent of approximately 897 square miles.

Respondents are directed to refer to the following sections and Appendices C - H of this RFP for technical specifications and a clear definition of the features and attributes which are considered deliverables, and therefore the responsibility of the contractor to provide.

- 9.2 Scope of Work: The contractor shall produce and deliver to each of the participating agencies digital orthoimagery, flight plan map including ground control, and a Full Analytic Aerial Triangulation (FAAT) report, to the standards stipulated in this section, Appendix C - H and elsewhere in this Request for Proposals.

All work required by the contract will be performed in conformance with these specifications and any contractual modifications to these specifications. Any deviation from the specifications, unless specifically authorized in writing by the Technical Project Manager overseeing the part of the project in question, shall be sufficient cause for rejecting any part or all of the work performed.

The technical specifications in the main body of the RFP apply to all of the work completed as a part of the project unless waived in writing by the committee administering the project. The additional specifications in each of the appendices will be administered by the Technical Project Manager designated by that agency in the final contract/s.

- 9.3 Technical Specifications: The imagery shall be flown in color. The respondent shall clearly detail the scale or scales needed to accomplish the digital orthoimagery. While the most recent aerials followed the National Map Accuracy Standards (NMAS), the COAGA 2019 understands that there is the American Society for Photogrammetry and Remote Sensing (ASPRS) Accuracy Standards as well. It is expected that the deliverables from this contract shall have an overall average accuracy of +/- 2.5 feet or better. In the areas where 3-inch pixel resolution is specified, the accuracy should meet the appropriate standards for 1" = 50' scale mapping 6-inch pixel = 1" = 100'). The respondent shall address the issue of the different accuracy between NMAS and ASPRS as it relates to this project, and whether it is feasible to increase the accuracy of the current datasets.
- 9.4 Flight The respondent shall detail flight and equipment specifications for the flight, including such information as endlap, sidelap, tilt and crab. The respondent shall also clearly indicate the process to insure the accuracy of the data compiled.
- 9.5 Project Area: See Appendix A for the project limit. Aerials shall be taken to obtain complete coverage of the designated flight areas with a minimum of a 200-foot buffer outside of the designated flight areas. In areas where City limits are in a portion of a PLSS section, the deliverables shall include the complete section.

- 9.6 Conditions During Imagery: The aerial photography must be obtained when the sky is clear of clouds, haze, smoke, dust, or any other aerial particles that may degrade the image. Ground features must be free of snow and ice. All unmanaged water bodies (lakes and streams) must not be at flood levels – photo acquisition must not take place within 2 days after a rainfall of 0.5 inches or greater or within 5 days after a rainfall of 2 inches or greater. Further, all deciduous trees must be in a leaf off state to ensure minimum ground obstruction from the existing tree canopy. Sun angle will not be less than 35 degrees. Respondents should describe how they will ensure that these condition constraints will be managed and met as part of the data acquisition.
- 9.7 Flight Plan: The strips of imagery shall be flown in conformance with a plan developed by the contractor and approved by the COAGA 2019. All strips shall be flown as straight as possible and shall be void of crab, tilt and altitude variation to the extent that they afford good stereoscopic coverage of the entire minimum areas. The project shall be flown on or near the date agreed to by the Contractor and the COAGA 2019.
- 9.8 Re-Flights: The contractor at no additional cost to participating COAGA 2019 agencies shall correct unacceptable aerial imagery with the re-flight coverage overlapping the accepted imagery by a sufficient amount to provide continuous stereoscopic coverage.
- 9.9 Aerial Sensor and Equipment: Respondents shall include in their proposals detailed information on type of sensor and equipment used for aerial imagery and control, including airborne GPS equipment if applicable. Aerial sensors used to acquire data must have current USGS certification or USGS digital aerial sensor type certification.
- 9.10 Aerotriangulation: Respondents shall include in their proposals detailed information on how the fully analytical aerotriangulation (FAAT) for control will be accomplished to meet accuracy guidelines outlined in this RFP, and whether Airborne GPS control points or ground control points will be used or if a combination of the two methods is suggested. Contractor must specify if additional ground control is needed or should be set. It is expected that the ground survey control will be performed under the supervision of a professional surveyor registered in the State of Oklahoma and experienced in geodetic control.
- 9.11 Scale and Accuracy of Orthophoto Images: See Appendix B.
- 9.12 Format For this project, all imagery will be output as tiled uncompressed TIFF formatted files associated with a TIFF World header file. Each primary image will cover an area approximately a PLSS section unless recommended otherwise. These images will be imported into SDE and other formats depending on community. The contractor shall also provide a project-wide MrSID image viewable by current versions of ArcGIS.
- 9.13 Pixel Resolution: The maximum horizontal ground resolution of the base digital orthophoto pixel size shall be no larger than 6 inches (.5 foot) except in those areas of the project requiring 3-inch (.25 foot) pixels. The digital orthophoto pixels may be delivered in a multiple resolution format for viewing enhancement software or allow for an Image pyramid for Digital Ortho Display.
- 9.14 Quality Control: The images and applicable reports will be examined to ensure that all processes and procedures used were adequate to meet the specifications agreed upon. Prior to authorizing full scale production, COAGA 2019 will examine sample images at each pixel resolution to ensure tonal quality in representative areas to be agreed upon by COAGA 2019 and the contractor. All images will undergo visual inspection to ensure the following:
- Completeness of data to cover the specified geographic extent, with no omissions or corrupt data.
 - Tonal balancing problems across the block.

- Ground Sample Distance to ensure that it meets the specified resolution.
- Mis-joins between linear features
- Cloud cover, smoke/haze, corrupt data, and void areas.
- Extreme tonal or color variation across seamlines.
- Extreme tonal or color variations in water features.
- Excessive horizontal displacement along seamlines in images
- Excessive tilt in bridges, buildings, and other raised features.
- Transportation features obstructed by buildings or shadows.
- Clipping of features (e.g. radio towers, water tanks, buildings) at tile boundaries.
- Building/structure warp that may indicate bad elevation data.
- Smearing.
- Evidence of over saturation or under saturation as a result of image processing or histogram manipulation.
- Evidence of image compression.

9.15 Attribute Data: All required nongraphic attributes for the geodatabase are identified in Appendices C - H of this RFP. In the event that necessary attribute data is missing, confused, or unreadable on any source material, the contractor will contact the appropriate Technical Project Manager designated in the final contract(s) for assistance. In cases concerning minor irregularities in the data or source maps where the answer is obvious or defined by precedent, the contractor may act to resolve the problem on his own initiative thereby reducing work stoppages and interruptions. When this occurs, the appropriate Technical Project Manager shall be informed of the action that the contractor took within 24 hours and the contractor will document how the problem was resolved.

9.16 Graphic Standards: Graphic component placement shall follow good cartographic practices so as to ensure aesthetic presentations of displays and plots. It is the responsibility of the Contractor to ensure that no overshoot or undershoot (closure and snapping) errors go unresolved and that proper topology exists. COAGA 2019 will leave the exact setting of the snap tolerances to the discretion of the Contractor, knowing that different map areas sometimes require different tolerances to be set. The Contractor is hereby informed that any data submitted that is shown to contain dangles, overshoots, or any other errors that result from the incorrect setting of tolerances will be unacceptable.

9.17 Feature Placement Methods: Unless otherwise specified in this RFP, Respondents shall include in their proposals suggested placement methods for positioning all features that are to be captured from the source materials. Respondents shall detail those methods, as well as the accuracy that they expect to achieve by employing those methods.

COAGA 2019 recognizes that there are different methods of data conversion. Deviations from standard accepted methods of conversion such as coordinate geometry and controlled graphic placement, which do not detract from the intended scope, quality and accuracy of data conversion may be accepted at the approval of the appropriate Technical Project Manager(s).

9.18 Digital construction requirements: The Respondent must adhere to the following digital graphic construction requirements:

- Edge-matching — All digital conversion units (maps) must be both visually and coordinate edge-matched with adjacent sheets. No edge-match tolerance will be allowed. Attributes for splittable features must also be identical.

- Common Boundaries — All features that share a common boundary, regardless of map layer, must have exactly the same digital position of that feature in all common layers.
- Point Duplication — No duplication of points within a data string is permitted.
- Connectivity — Where graphic elements visually meet, they must also digitally meet. All confluences of line and point or node data must be exact; that is, no “overshoots,” “undershoots,” or “offsets” are permitted.
- Line Quality — A high quality cartographic appearance shall be achieved. Transitions from straight lines to arcs and other curvilinear elements shall be smooth, with angular inflections at the point of intersection. The digital representation must not contain extraneous data. There should be no jags, hooks, or zero length segments. Any lines that are straight, or should be straight, should be digitized using only two points that represent the beginning and ending points of the line.
- Polygon Closure — Polygons and regions must be topologically correct per the Geodatabase data model and should contain no duplicate arcs.
- Graphic Precision — All graphic elements must contain positional coordinates significant to one ten thousandth (.0001) of a foot. Specification of Deliverables: The Contractor will deliver formatted Geodatabase, orthophoto data in TIFF, MrSID formatted files (transparent backgrounds) and JP2000, and topographic data in both an ESRI formatted Geodatabase and AutoCAD format, all of which are agreed upon by the participating agency and the Contractor.

9.19 Topographic data: Data collection methods must support the development of a digital terrain model (DTM) sufficient to attain a horizontal and vertical accuracy to support 1' contour generation at 1" = 100' scale (or better) or 2 foot contours (or better) depending on the requirements of the requesting agency. The methods must conform to the latest version of the ASPRS Positional Accuracy Standards for Digital Geospatial Data (2014). All digital elevation models (DEM) must be hydro-flattened and breaklines used for this process must be maintained as part of final deliverables. If lidar is used to develop the topographic data the collection of the lidar must comply with the standards put forth in Lidar Base Specification Version 1.0 published by the USGS: Chapter 4 of Section B, U.S. Geological Survey Standards, Book 11, Collection and Delineating of Spatial Data published in October 2014.

A report on the assessed absolute vertical accuracy of the bare earth-surface surface in accordance with the guidelines set forth in the ASPRS Positional Accuracy Standards for Digital Geospatial Data (2014) is required.

The respondent must identify all equipment and methods used to collect the topographic data and how they meet ASPRS/USGS Standards.

9.20 Accuracy: The Contractor shall use accepted map compilation procedures and equipment to achieve the levels of accuracy, detail, and quality required by these specifications. Based on the source documents and proven past performance, the Contractor shall prepare statements of achievable levels of absolute and relative accuracy for the compiled features.

9.21 Acceptance Procedures: The participating agencies of COAGA 2019 will report any problems encountered in a timely manner, and in a standard format agreed to with the Contractor.

9.22 Ownership of Deliverables: The participating agencies will retain ownership of all source data and documents; database schema components; custom software; and digital and

hard copy products procured, created, or generated in the development of the document database. These records, data, programs, and other materials shall be surrendered to participating agencies upon completion or termination of the project.

Respondents, the Contractor or subcontractor shall not make any claim or right of ownership under patent or copyright law to any of the materials, data, or programs created specifically for this project. The Contractor may not reveal, share, or sell any of these products without written permission of the agency or agencies for which it was written. These terms and conditions exclude any pre-existing conversion software the Contractor may have developed or commercial software acquired prior to beginning work on this project.

Section 10: Cost Proposal Forms

The COAGA 2019 is seeking firm fixed prices for the performance and delivery of digital orthoimagery and flight plan map. Prices shall cover all necessary work, materials, supplies, data preparation, entry, translation and quality control, etc. Reproduction, travel and other direct and indirect costs should also be included.

It is the responsibility of the Respondent to verify any count information used in estimating the cost of conversion. These estimates are based on the most current information available.

The following firm fixed cost worksheet should be filled out as a minimum. ***The worksheet must be accompanied by the non-collusion affidavits found in Appendix I: Forms.***

10.1 Firm Fixed Unit Costs: Appendix B – Digital Color Orthoimagery (TIFF)

City of Edmond (127 miles @ 3")	_____
City of Del City (8 miles @ 3")	_____
City of Midwest City (42.43 miles @ 3")	_____
City of Moore (21.9 miles @ 6")	_____
City of Norman (164 miles @ 6" <u>and</u> 92 miles @3")	_____
Canadian County (ACOG) (approx.. 897 miles @ 6")	_____
<u>OR</u> (897 miles @ 12")	_____

Optional mosaic products:

1. MrSID and JP2000 of City of Edmond	_____
2. MrSID and JP2000 of City of Del City	_____
3. MrSID and JP2000 of City of Midwest City	_____
4. MrSID and JP2000 of City of Moore	_____
5. MrSID and JP2000 of City of Norman	_____
6. MrSID and JP2000 of Canadian County - ACOG	_____
7. MrSID and JP2000 of Entire Project Area - ACOG	_____

10.2 Optional Mapping Deliverables

City of Edmond


Planimetric Change Detection & Collection - Pilot Study Area Cost	_____
Planimetric Change Detection & Collection - Remainder of the City	_____
LiDAR Collection and interpolation of the HE-DTM into 1 foot Contours - Pilot Area	_____
LiDAR Collection and interpolation of the HE-DTM into 1 foot Contours - Remainder of the City	_____

City of Norman - See Appendix G for Collection Areas and Features

Planimetric Change Detection & Collection 1" = 50' - Pilot Study Area Cost	_____
Planimetric Change Detection & Collection 1" = 100' - Pilot Study Area Cost	_____
Planimetric Change Detection & Collection 1" = 50' - Remainder of the Collection Area	_____
Planimetric Change Detection & Collection 1" = 100' - Remainder of the Collection Area	_____
LiDAR Collection and interpolation of the HE-DTM into 1 foot Contours - Pilot Area	_____
LiDAR Collection and interpolation of the HE-DTM into 2 feet Contours - Pilot Area	_____
LiDAR Collection and interpolation of the HE-DTM into 1 foot Contours - Remainder of the Collection Area	_____
LiDAR Collection and interpolation of the HE-DTM into 2 feet Contours - Remainder of the Collection Area	_____
FEMA compliant Vertical Accuracy Report (60 check points)	_____

In addition, the Respondent may propose alternative pricing methods per Section 8.13. The participating agencies of COAGA 2019 reserve the right to limit the scope of the project.

[Appendix A: Project Overview Map](#)



Appendix B: Project Deliverables

Scope: The project area covers 1,351.85 square miles depending upon the options taken. Some cities participating in this project stores their imagery in ArcSDE. Their delivery must be in a seamless format compatible with ArcSDE. The other entities have their requests in their specific Appendices. The cities have major investments in base maps and survey monuments that are tied to specific coordinate systems and datum (Attachments to Appendix B, Figure 1). Because of the need to integrate the data collected by this project into the existing datasets, different coordinate systems will be used for final deliverables.

Projection: Below are the coordinate systems and datum currently being used by participating agencies:

Edmond, Del City, Midwest City and Canadian County:

Coordinate system: Oklahoma State Plane, North Zone 3501

Horizontal Datum: NAD83

Vertical Datum: NAVD88

Spheroid: GRS 1980

Map Units: US Survey Feet

Moore and Norman:

Coordinate system: Oklahoma State Plane, South Zone 3502

Horizontal Datum: NAD83 (HARN) - 1993 adjustment

Vertical Datum: NAVD88

Spheroid: GRS 1980

Map Units: US Survey Feet

Accuracy: The final scale will be NMAAS 1" = 50', 1" = 100', or 1" = 200' based upon the alternative chosen. The respondent shall detail the possibility of meeting the ASPRS Standard for Class 1 Map Accuracy for such scale mapping. Otherwise, it shall meet the National Map Accuracy Standard for such scale mapping.

Tiling Scheme: The tiling scheme will be based upon the Public Land Survey System (PLSS) modified to make certain that it overlaps each individual city's boundary by at least 200 feet. It is the responsibility of the contractor to use the generic PLSS grid and the grids of the participating cities determine the best way to create a region-wide grid.

Deliverables: All imagery will be output as tiled uncompressed TIFF formatted files associated with a TIFF World header file at the resolution and accuracy selected. The images will follow the tiling scheme proposed by the contractor and agreed upon by COAGA 2019. These images will be imported into SDE, or other as stated. All tiles will also be delivered resampled to 1-foot resolution in uncompressed TIFF formatted files associated with a TIFF World header file. The contractor shall also provide a project-wide MrSID image viewable by current versions of ArcGIS. A summary of major work products is below. Each city will be delivered a copy of the tiles which cover its extent and understand that there will be a 200' project buffer.

Required for selected alternative:

- Flight line diagram
- Calibration report

- FAAT report
- MrSID of Project in NAD83

Optional Products:

1. MrSID and JP2000 of Edmond
2. MrSID and JP2000 of Del City
3. MrSID and JP2000 of Midwest City
4. MrSID and JP2000 of Moore
5. MrSID and JP2000 of Norman
6. MrSID and JP2000 of Canadian County - ACOG
7. MrSID and JP2000 of Entire Project Area - ACOG

[Appendix C: City of Edmond](#)

Background

The City of Edmond project covers an area of approximately 127 square miles. The City has a population of approximately 92,000. There are 723 miles of streets, 48,770 address points, and approximately 65,185 buildings. Elevations within the City limits range from 899 to 1,237 feet above sea level. The City of Edmond contracted with Sanborn Map Company, Inc in 2018 to update its orthophoto, planimetric and topographic data.

Aerial photography

3-inch (0.25 foot) pixels resolution color ortho photography (2018 date)

Planimetrics (2018 Date)

Hydrography – linear and polygon features
Street centerlines
Railroads
Building footprints – to include building heights
Edge of pavement
Driveways
Sidewalks
Sidewalk Centerlines
Vegetation (Tree mass)
Single Trees in the Right-of-Way along section line roads
ParkingLots
Fences

Topography (2018 Date)

1-foot elevation contours
Spot elevations
Hydrologically enforced Digital Elevation Model (DTM) – breaklines and masspoints

The City of Edmond relies on a robust GIS to perform business operations. All data is stored in a 10.1 SP1 ArcSDE repository located in a MS SQL Server 2012 database. At this time the City of Edmond is seeking to upgrade in 2018-2019.

Respondents are directed to refer to the RFP, the following sections and Appendices A and B of this RFP for technical specifications and a clear definition of the features and attributes that are considered deliverables, and therefore the responsibility of the Contractor to provide.

Objectives

Obtain updated color digital orthophotography according to NMAS 1" = 50' standards – 3" (0.25 foot) pixel resolution.
Obtain updated Hydrologically Enforced DTM and 1-foot elevation contours.
Update existing GIS base datasets according to NMAS 1" = 50' standards.

Scope of Work

The Contractor shall produce and deliver to the City of Edmond photogrammetric change detection and update of the existing hydrological enforced Digital Terrain Model (HE-DTM) with 1-foot contour database with labels and spot elevations, photogrammetric change detection and collection of the planimetric features to the standards stipulated in this section and elsewhere in this Request For Proposals. The Contractor shall furnish all materials, equipment, labor, management, insurance, postage, and transportation necessary to complete this work. The Respondent should propose the best procedures and commonly accepted professional techniques in order to assure complete compliance with this RFP.

All work required by the contract will be performed in conformance with these specifications and any contractual modifications to these specifications. Any deviation from the specifications, unless specifically authorized in writing by the GIS Project Manager, shall be sufficient cause for rejecting any part or all of the work performed.

Technical Specifications

The initial planimetric data and most recent aerials followed the National Map Accuracy Standards (NMAS). It is expected that the deliverables from this contract shall have an overall average accuracy of 1 inch = 50 feet. The respondent shall address the issue of the different accuracies of the other participating agencies as it relates to this project, and how they will maintain or improve the accuracy of the City of Edmond's current datasets.

Planimetric Features

The planimetric data to be updated is road edges (paved, unpaved, trail centerlines, sidewalks, and driveways), parking lots, buildings, (minimum size is 12' x 10'), hydrology (including drainage features such as ditches), railroad centerlines, street centerlines, sidewalk centerlines, tree mass outlines, single trees in the R.O.W (of section line roads) and fences that follow along R.O.W lines and lots (parcels) to depict ownership. Sample digital data may be provided as an attachment. Respondents are also directed to refer to Appendix C – Attachment D of this RFP for a clear definition of the features and attributes that are considered deliverable, and therefore the responsibility of the Contractor to populate into the GIS database as part of the conversion effort. Respondents shall indicate in their technical plan of operations suggested data conversion techniques for the compilation of source map data.

Please see Appendix C – Attachment C for a map of building permits issued since the last flight in February 2018 to show where building has occurred. Since there continues to be development in the City, these areas should not be considered all-inclusive for the change detection portion of this RFP. The City has placed some building footprints from plans to depict construction in the building layer. These are identified by attributes. The contractor shall update these structures based on an accurate representation from the photography. If there are any physical changes to any existing structure, due to additions or modifications, the contractor shall update the geometry of those structures as part of the change detection.

Pilot Study For Planimetric data. The Pilot Study is necessary for the City of Edmond to evaluate the process of detecting change and updating the planimetric data. The Pilot

will be used to refine the scope of the remaining data conversion project in terms of quality, accuracy and, timeliness. An important component of this phase will be to clarify, and test procedures used by the Contractor and the City to complete this project.

Selected Pilot Area The Pilot Study Area section (Section 14 Township 14 North, Range 2 West) was chosen to be the pilot in this conversion process because of its development. The Pilot Study Area is a one square mile section with approximately 239 parcels with approximately 46 building permits.

Pilot Study Process In the City of Edmond's conversion plan, the Contractor will be supplied with source data to use in the conversion process. The source material for this pilot will be a version of the planimetric feature dataset. The pilot study process will give the Contractor and the City of Edmond the opportunity to work with the source data and to identify and resolve any questions or problems that arise as actual data conversion is initiated. It gives both parties, prior to full production, the time needed to implement procedures and resolve problems reducing delays and reworks.

Scale and Accuracy of Planimetric Data The final scale will be 1" = 50' and the respondent shall meet the National Map Accuracy Standard for such scale mapping. All spatial data shall conform to the following:

Coordinates/Projection:	State Plane Coordinate System,
Zone:	Oklahoma North, FIPS Zone 3501
Horizontal Datum:	NAD83
Map Units:	Feet

Topographic Data - Optional

The existing one-foot contour topographic mapping data was collected LiDAR data. The City of Edmond's Stormwater/Drainage Engineering division requires a hydrologically enforced DTM to ensure a high level of detail with regards to the breaklines for the generation of one-foot contours and spot elevations at traditional locations. The contractor will provide 3D breaklines at abrupt changes in slope. Breaklines will be collected at appropriate areas, produced by either naturally or man-made features. The contractor will also digitize masspoints in addition to breaklines, taking careful note of high and low spots. Respondents shall indicate in their technical plan of operations suggested data conversion techniques for the compilation of source map data.

The City is requesting that respondents address the ability to support the update of 1-foot contours with the aforementioned requirements of it being drainage enforced, as well as it meeting the vertical accuracy of one-half of the contour level.

The respondents should refer to Appendix C - Attachment D for the data dictionary and required geodatabase and Autocad DWG formats of the topographic data.

Pilot Study For Topographic data. The Pilot Study is necessary for the City of Edmond to evaluate the generation of 1-foot contour from the Digital Terrain Model. The Pilot will be used to refine the scope of the remaining data conversion project in terms of quality, accuracy and, timeliness. An important component of this phase will be to clarify and test procedures used by the Contractor and the City to complete this project.

Selected Pilot Area The Pilot Study Area section (Section 14 Township 14 North, Range 2 West) was chosen to be the pilot in this conversion process because of its development. The Pilot Study Area is a one square mile section with approximately 239 parcels with approximately 46 building permits.

Pilot Study Process The pilot study process will give the Contractor and the City of Edmond the opportunity to work with the source data and to identify and resolve any questions or problems that arise as actual data conversion is initiated. It gives both parties, prior to full production, the time needed to implement procedures and resolve problems reducing delays and reworks.

Scale and Accuracy of Topographic Data

The respondent shall detail how the contours will be generated and verified to ensure the vertical accuracy of one-half the contour level. The respondent shall also detail the possibility of meeting ASPRS Standard for Class 1 Map Accuracy for such scale mapping that supports 1-foot contour. Otherwise, it shall meet the National Map Accuracy Standard for such scale mapping. All spatial data shall conform to the following:

Coordinates/Projection:	State Plane Coordinate System,
Zone:	Oklahoma North, FIPS Zone 3501
Horizontal Datum:	NAD83
Elevation Datum:	NAVD88
Ellipsoid:	GRS83
Map Units:	US Survey Feet

Attribute Data

All required nongraphic attributes for the geodatabase are identified in Appendix C – Attachment D of this RFP. In the event that necessary attribute data is missing, confused, or unreadable on any source material, the Respondent will contact the City of Edmond GIS Project Manager for assistance. In cases concerning minor irregularities in the data or source maps where the answer is obvious or defined by precedent, the Contractor may act to resolve the problem on his own initiative thereby reducing work stoppages and interruptions. When this occurs, the City of Edmond GIS Project Manager shall be informed of the action that the Contractor took within 24 hours and the Contractor will document how the problem was resolved.

The City of Edmond is seeking firm fixed prices for the performance and delivery of digital orthoimagery and flight plan map, optionally Planimetric Change Detection & Collection of Planimetric and Collection of LiDAR derived HE-DTM into 1-foot Contours. Prices shall cover all necessary work, materials, supplies, data preparation, entry, translation and quality control, etc. Reproduction, travel and other direct and indirect costs should also be included.

COE acknowledges that the proposer may be required to make some assumptions about the city's environment and specific requirements and operations. Any assumptions made by the proposer in regard to this RFP shall be documented in this section.

It is the responsibility of the Respondent to verify any count information used in estimating the cost of conversion. These estimates are based on the most current information available.

Deliverables

Cost Worksheet in Section 10 of the RFP must be completed.

Firm Fixed Unit Costs

City of Edmond: (127 square miles @ 3")

Digital Orthophotos

1. Aerial Triangulation Report
2. A set of color digital orthos in georeferenced TIFF format (uncompressed)
3. A full citywide color MrSID mosaic (40:1 compression)

Optional Mapping Deliverables: - see Appendix C – Attachment D for geodatabase design

Planimetrics/GIS Base Data

Planimetric Change Detection & Collection - Pilot Study Area Cost

Planimetric Change Detection & Collection - Remainder of the City

Topography/Lidar:


LiDAR Collection and interpolation of the HE-DTM into 1-foot Contours- Pilot Area


LiDAR Collection and interpolation of the HE-DTM into 1-foot Contours - Remainder of the City


- Vertical Accuracy Report
- ASCII Digital Elevation Model (DEM) data
- Hydro Flattened/Enforced, Bare Earth DEM
- Spot Elevations
- Raw Point File fully compliant with LAS 1.4
- Topographic databases in ArcGIS Geodatabase and AutoCAD dwg formats

Metadata

1. Metadata must be included in all geodatabases deliveries for all feature classes using the FGDC format.
2. Metadata should include: author information, a description of the dataset, data capture techniques, definitions for all fields, subtypes and domain code descriptions, statement of accuracy, compilation scale, and dates of the completed compilation.







Appendix C – Attachment D

Edmond Geodatabase Design – Planimetric and Topographic Data

This version of the City of Edmond geodatabase data model follows a standard planimetric data model. The following describes the GIS database design for the feature dataset. The Contractor will conform their attribute capture and population of the data sets from the data model illustrated below.

The planimetric data compiled includes road edges (paved, unpaved, trail centerlines, sidewalks, and driveways), parking lots, buildings (minimum size is 12'x10'), hydrology (including drainage ditches), railroad centerlines, street centerlines, sidewalk centerlines, tree mass outlines and single trees in the right of way, and fences that show ownership. Updates include any modifications to existing features such as road widenings and building additions or demolitions.

The topographic data set includes breaklines and masspoints feature class in addition to the contour lines and spot elevations.

The following pages show the feature attribute tables in detail. Whenever codes or a set of valid values is used for an attribute, a domain table is utilized. The information in the lookup tables is not included in this document.

The Respondent is encouraged to add to any aspect of this design in order to better meet the needs of the city of Edmond. Examples of such modifications might include adding new feature types or creating a domain table in the geodatabase for definitions of allowable values. However, the Contractor will be required to report any such changes to the City and to request prior approval for any change, which would preclude creating layers in the specified formats.

Data File-Type Information and System Requirements:

Planimetric Data

Buildings (polygon)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
TYPE	Type	Long Integer	4	Subtype code (see below).
UPDATED	Updated	Date	8	Feature updated date.
SHAPE	Shape	Geometry	0	Feature geometry.
ASSET_TYPE	Asset Type	Text	20	Building Type.
FIRE_SUPPRESSION	Fire Suppression	Text	8	Buildings with sprinklers.
ELEVATION	Elevation	Double	8	Building heights
MODIFIED BY	Modified By	Text	30	Modify by
MODIFIED DATE	Date Modified	Date	*	Date of Modification

STATUS	Status	Text	20	Status of building
SHAPE.AREA	SHAPE.AREA	Double	8	Area of feature.
SHAPE.LEN	SHAPE.LEN	Double	8	Length of feature.

Building Subtypes

Code	Description
0	Government Building
1	Building
2	Foundation
3	Ruin
4	Tank
99	Out Areas

Fence (line)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
SHAPE	Shape	Geometry	0	Feature geometry.
TYPE	Type	Long Integer	4	Subtype code (see below).
UPDATED	Updated	Date	8	Feature updated date.
SHAPE_LENGTH	Shape_Length	Double	8	Length of feature (in units).

Fence Subtypes

Code	Description
1	Fence

Hydrology (polygon)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
SHAPE	Shape	Geometry	0	Feature geometry.
DISPLAY	Display	ShortInteger	2	Display code (not used).
TYPE	Type	Long Integer	4	Subtype code (see below).
NAME	Name	Text	35	Name of water body.
UPDATED	Updated	Date	8	Feature updated date.

Shape_Length	Shape_Length	Double	8	Length of features (in units).
Shape_Area	Shape_Area	Double	8	Area of features (in units)

Hydrology Subtypes

Code	Description
1	River
2	Lake, Reservoir
3	Pond
4	Island
5	Irrigation Canal
6	Creek
99	Out Area

Hydrology Lines (line)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
SHAPE	Shape	Geometry	0	Feature geometry.
TYPE	Type	Long Integer	4	Subtype code (see below).
DISPLAY	Display	ShortInteger	4	Display code (not used).
NAME	Name	Text	35	Hydrology line name.
UPDATED	Updated	Date	8	Feature updated date.
Shape_Length	Shape_Length	Double	8	Length of features (in units).

Hydrology Line Subtypes

Code	Description
1	River
2	Lake, Reservoir
3	Pond
4	Island
5	Irrigation Canal
6	Creek
7	Irrigation Ditch
99	Tile Edge

Parking Lot (polygon)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
SHAPE	Shape	Geometry	0	Feature geometry.
TYPE	Type	ShortInteger	2	Subtype code (see below).
UPDATED	Updated	Date	8	Feature updated date.
Shape_Length	Shape_Length	Double	8	Length of features (in units).
Shape_Area	Shape_Area	Double	8	Area of features (in units).

Parking Lot Subtypes

Code	Description
1	Parking Lot
99	Out Areas

Pavement (polygon)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
SHAPE	Shape	Geometry	0	Feature geometry.
TYPE	Type	ShortInteger	2	Subtype code (see below).
DISPLAY	Display	ShortInteger	2	Display code (not used).
UPDATED	Updated	Date	8	Feature updated date.
Shape_Length	Shape_Length	Double	8	Length of features (in units).
Shape_Area	Shape_Area	Double	8	Area of features (in units).

Pavement Subtypes

Code	Description
1	Paved Road
2	Unpaved Road
3	Bridge
4	Sidewalk
5	Driveway
6	Unpaved Driveway
99	Out Areas

Pavement Lines (line)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
SHAPE	Shape	Geometry	0	Feature geometry.
TYPE	Type	Long Integer	4	Subtype code (see below).
DISPLAY	Display	ShortInteger	2	Display code (not used).
UPDATED	Updated	Date	8	Feature updated date.
Shape_Length	Shape_Length	Double	8	Length of features (in units).

Pavement Lines Subtypes

Code	Description
5	Trails
9	Bike Paths
99	Tile Edge

Railroad (line)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
SHAPE	Shape	Geometry	0	Feature geometry.
TYPE	Type	ShortInteger	2	Subtype code (see below).
DISPLAY	Display	ShortInteger	2	Display code (not used).
NAME	Name	Text	35	Railroad name.
UPDATED	Updated	Date	8	Feature updated date.
Shape_Length	Shape_Length	Double	8	Length of features (in units).

Railroad Subtypes

Code	Description
1	Railroad Centerline

Road Centerline (line)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
SHAPE	Shape	Geometry	0	Feature geometry.
TYPE	Type	ShortInteger	2	Subtype code (see below).
DISPLAY	Display	ShortInteger	2	

NAME	Name	Text	35	Road centerline name.
UPDATED	Updated	Date	8	Feature updated
Shape_Length	Shape_Length	Double	8	Length of features (in units).
Shape_Area	Shape_Area	Double	8	Area of Features (in units).

Road Centerlines Subtypes

Code	Description
1	Paved Road Centerline
2	Unpaved Road Centerline
3	Sidewalk Centerline

Single Trees (point)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
SHAPE	Shape	Geometry	0	Feature geometry.
TYPE	Type	LongInteger	4	Subtype code (see below).
UPDATED	Updated	Date	8	Feature updated
Shape_Length	Shape_Length	Double	8	Length of features (in units).
Shape_Area	Shape_Area	Double	8	Area of Features (in units).

Single Trees Subtypes

Code	Description
1	Coniferous Tree
2	Deciduous Tree

Vegetation (polygon)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
SHAPE	Shape	Geometry	0	Feature geometry.
TYPE	Type	LongInteger	4	Subtype code (see below).
UPDATED	Updated	Date	8	Feature updated date.
Shape_Length	Shape_Length	Double	8	Length of features (in units).

Shape_Area	Shape_Area	Double	8	Area of Features (in units).
------------	------------	--------	---	------------------------------

Vegetation Subtypes

Code	Description
1	Tree Line
2	Tree Line Opening

Topographic Data

Contours (line)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
TYPE	Type	LongInteger	4	Subtype code (see below).
UPDATED	Updated	Date	36	Feature updated date.
ELEVATION	Elevation	Double	8	Elevation.
SHAPE	Shape	Geometry	0	Feature geometry.
Shape_Length	Shape_Length	Double	8	Length of features (in units).

Contour Subtypes

Code	Description
1	Index Contour
2	Intermediate Contour
3	Hidden Index Contour
4	Hidden Intermediate Contour

Spot Elevations (point)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
TYPE	Type	LongInteger	4	Subtype code (see below).
UPDATED	Updated	Date	36	Feature updated date.
ELEVATION	Elevation	Double	8	Elevation.
SHAPE	Shape	Geometry	0	Feature geometry.

Spot Elevation Subtypes

Code	Description
1	Ground Elevation
2	Bridge Elevation
3	Water Elevation

Obscured Areas (polygon)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
TYPE	Type	LongInteger	4	Subtype code (see below).
UPDATED	Updated	Date	36	Feature updated date.
SHAPE	Shape	Geometry	0	Feature geometry.
Shape_Area	Shape_Area	Double	8	Area of Features (in units).
Shape_Length	Shape_Length	Double	8	Length of features (in units).

Obscured Areas Subtypes

Code	Description
1	Obscured Area

DTM Breaklines (line)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
TYPE	Type	LongInteger	4	Subtype code (see below).
UPDATED	Updated	Date	36	Feature updated date.
SHAPE	Shape	Geometry	0	Feature geometry.
Shape_Length	Shape_Length	Double	8	Length of features (in units).

DTM Breaklines Subtypes

Code	Description
1	Breakline

DTM Mass Points (points)

Attributes	Alias	Data Type	Width	Definition
OBJECTID	OBJECTID	OID	4	Internal feature number.
TYPE	Type	LongInteger	4	Subtype code (see below).
UPDATED	Updated	Date	36	Feature updated date.
ELEVATION	Elevation	Double	8	Elevation.
SHAPE	Shape	Geometry	0	Feature geometry.

DTM Mass Points Subtypes

Code	Description
1	Mass Point

Topographic Data CAD Format Requirements

CAD File Objects:

Each .dwg group layer contains 5 object classes. These object classes include:

Annotation object or a annotation.	An object layer that is used to store text related to another CAD drawing title block. Each spot elevation point contains
Point represented	An object layer that stores CAD points. Spot elevations are points.
Polyline this	An object layer that is used to store CAD lines. Each contour line in object class is represented as a line.
Polygon CAD	An object class that is used to store closed areas, or polygons in the and GIS drawing environment. Contour lines that are closed are represented as polygons.
MultiPatch	This geometry type is used for storing 3D objects - such as buildings, geological bodies, 3D no-fly zones, etc - in both the geodatabase and shapefile formats.

CAD Data Attributes:

The following table provides a description of each CAD field.

Name	Type	Width	Description	Feature class
FID	Object ID	4	Unique feature identifier.	All
Shape	Shape	*	Geometric shape of entity.	All
Entity	String	16	The type of CAD entity that the feature represents. Entity and element are synonymous.	All
Handle	String	16	The CAD unique identifier for entities and elements.	All
Layer	String	255	A logical grouping of data in a drawing. Layers can contain a mixture of feature types.	All
LyrFrzn	Short	2	The CAD frozen status of the layer. Frozen layers are not displayed.	All
LyrLock	Short	2	The CAD locked status of the layer. Locked layers are displayed.	All
LyrOn	Short	2	The CAD display status of the layer.	All
LyrVPFrzn	Short	2	The CAD frozen status of the layer's viewport. Frozen layers are not displayed.	All
LyrHandle	String	16	The CAD-maintained internal identifier for a layer.	All
Color	Short	2	The display color of the entity.	All
EntColor	Short	2	The assigned color of the entity.	All
LyrColor	Short	2	The color of the layer in which the entity resides.	All
BlkColor	Short	2	The color of the block with which the entity is associated.	All
Linetype	String	255	The display line type of the entity.	All
EntLinetype	String	255	The assigned line type of the entity.	All
LyrLinetype	String	255	The line type of the layer in which the entity resides.	All
BlkLinetype	String	255	The line type of the block with which the entity is associated.	All
Elevation	Double	8	The z-coordinate value of an entity. In cases where the z-coordinate values of an entity's vertices vary, the z-coordinate value of the vertex encountered will be used.	All
Thickness	Double	8	The extrusion distance of an entity.	All
LineWt	Short	2	The display line weight of an entity.	All
EntLineWt	Short	2	The assigned line weight of an entity.	All
LyrLineWt	Short	2	The line weight of the layer in which the entity resides.	All
BlkLineWt	Short	2	The line weight of the block with which the entity is associated.	All
RefName	String	255	Name of the parent object in which the entity resides.	All

LTScale	Double	8	The scale of the entity's line type.	All
Angle	Double	8	The rotation angle of an entity (in degrees).	Annotation/Point
ExtX	Double	8	X-coordinate extrusion value.	All
ExtY	Double	8	Y-coordinate extrusion value.	All
ExtZ	Double	8	Z-coordinate extrusion value.	All
DocName	String	255	Name of the CAD file.	All
DocPath	String	4096	Path of the CAD file.	All
DocType	String	255	Type of CAD file (by extension).	All
DocVer	String	16	Version of CAD file.	All
ScaleX	Double	8	X-coordinate scale value.	Annotation/Point
ScaleY	Double	8	Y-coordinate scale value.	Annotation/Point
ScaleZ	Double	8	Z-coordinate scale value.	Annotation/Point
<Attribute Tag>	Double	8	An object that is part of an insert that stores alphanumeric data.	All
<Attribute Tag>	Long	4	An object that is part of an insert that stores alphanumeric data.	All
<Attribute Tag>	String	15	An object that is part of an insert that stores alphanumeric data.	All
Style	String	255	Text style.	Annotation
FontId	Short	2	Text symbol ID number (specific to ArcGIS).	Annotation
Text	String	255	Text string.	Annotation
Height	Double	8	Text height.	Annotation
TxtWidth	Double	8	CAD text entity width factor.	Annotation
TxtOblique	Double	8	CAD text entity oblique angler.	Annotation
TxtGenType	String	32	CAD text generation type.	Annotation
TxtJust	String	32	CAD text entity justification parameter.	Annotation
VertAlign	String	32	CAD text entity vertical alignment parameter.	Annotation
TxtFont	String	255	CAD text entity font.	Annotation
TxtBoxHt	Double	8	CAD text entity bounding box height.	Annotation
TxtBoxWd	Double	8	CAD text entity bounding box width.	Annotation
TxtRefWd	Double	8	CAD multiline text width factor.	Annotation
TxtAttach	Short	2	CAD multiline text attachment parameter.	Annotation
TxtDir	Short	2	CAD multiline text direction parameter.	Annotation
LnSpace	Short	2	CAD multiline text spacing type.	Annotation
SpaceFact	Double	8	CAD multiline text spacing factor.	Annotation
TxtMemo	String	2048	Entire CAD text string.	Annotation

[Appendix D: City of Del City](#)

Background

The City of Del City has a population of 21,332 and is located in Oklahoma County. The City contracted with FUGRO in 2014 to update its orthophoto information. The city encompasses 7.52 square miles. The area of capture is 8 square miles. The last Ortho was flown in 2014.

They would like to have price estimates for 3" data.

Projection

All spatial data shall conform to the following projection:

Coordinates/Projection:	NAD_1983_StatePlane,
Zone:	Oklahoma_North_FIPS_3501_Feet
Horizontal Datum:	D_North_American_1983
Map Units:	US Survey Feet

Software Capability

The City of Del City currently has ArcGIS 10.2 and AutoCAD Map 2011.

Deliverables

The final ortho deliverables will be required to be in:

- GeoTIFF, uncompressed
- MrSID, compressed no greater than 15:1*
- Lossless JPEG 2000

*Note: No re-compression of compressed data is acceptable. Image mosaics shall be equal in quality to image tiles.

Final topological data to be delivered in Shapefiles, AutoCAD DWG files, etc.

Appendix E: City of Midwest City

Background

The City of Midwest City project covers an area of approximately 26.6 square miles – see 2019 DOP Areal Coverage Requirements map. Midwest City has a population of approximately 55,000. The City of Midwest City procured DOPs in 2010, 2013, and in 2015.

Respondents are directed to refer to the RFP, the following sections and Appendices A, B, and F of this RFP at the attachments to these sections for technical specifications deliverables, and therefore the responsibility of the Contractor to provide.

Objectives

1. Obtain updated color digital orthoimagery according to NMAS 1" = 50' standards - 3-inch pixel resolution for 42.43 square miles.

Scope of Work

The Contractor shall produce orthophotos with sufficient overlap and accuracy to photogrammetric change detection to meet National Map Accuracy Standards (NMAS) for 1 inch = 50 feet. The Contractor shall furnish all materials, equipment, labor, management, insurance, postage, and transportation necessary to complete this work. The Respondent should propose the best procedures and commonly accepted professional techniques in order to assure complete compliance with this RFP.

All work required by the contract will be performed in conformance with these specifications and any contractual modifications to these specifications. Any deviation from the specifications, unless specifically authorized in writing by the GIS Project Manager, shall be sufficient cause for rejecting any part or all of the work performed.

Technical Specifications

It is expected that the deliverables from this contract shall have an overall average accuracy of NMAS for 1 inch = 50 ft. The respondent shall address the issue of the different accuracies of the other participating agencies as it relates to this project, and how they will maintain or improve the accuracy of the City of Midwest City's current datasets.

Please note that some if not many of the City's monuments have been displaced or destroyed. Midwest City is attempting to obtain new monumentation prior to the flight of this contract. The Contractor is expected to confirm and/or add new monuments in order to achieve the desired accuracy of the DOPs.

Scale and Accuracy of Data:

The final scale will be 1" = 50' and the respondent shall meet the National Map Accuracy Standard for such scale mapping. All spatial data shall conform to the following:

Coordinates/Projection:	State Plane Coordinate System,
Zone:	Oklahoma North, FIPS Zone 3501
Horizontal Datum:	NAD83 (CORS96)
Vertical Datum:	NAVD88
Map Units:	US Survey Feet

Area of Work

The project area includes the entire area within the boundary as shown below – a total of 42.43 square miles.

Deliverables

The final orthophoto deliverables will be required to be in:


- Shapefile of tiling scheme/ortho index (tiled at approximately PLSS sections)
- Set of color DOPS in georeferenced TIFF, uncompressed, with an ESRI 10.6.1 compatible image catalog
- Set of MrSID compressed format no greater than 15:1* with an ESRI 10.6.1 compatible image catalog
- A full project area-wide color MrSID mosaic (1:15 compression)
- A full project area-wide color image resampled to 6-in resolution
- Lossless JPEG 2000
- DTM ASCII file in TIN generate format, ESRI 10.6.1 format and AutoCad format (optional)

*Note: No re-compression of compressed data is acceptable. Image mosaics shall be equal in quality to image tiles.

Cost Worksheet in Section 10 of the RFP must be completed.

2019 DOP Aerial Coverage Requirements City of Midwest City

Map Date:
11/1/2018



Appendix F: City of Moore

Background

Moore has a population of 52,361 and approximately 21.9 square miles. It is adjoining Oklahoma City on the north, east and west side of its city boundary and Norman and an incorporated area of Cleveland county on the south. Last Ortho was flown in 2017. This year the city will only be getting aeriels.

The City of Moore will provide the Contractor with all of our data from the past project, as well as current street centerline, parcel and city boundary data, and city monuments.

Projection

All spatial data shall conform to the following:

Coordinates/Projection:	State Plane Coordinate System,
Zone:	Oklahoma South, FIPS Zone 3502
Horizontal Datum:	HARN NAD83
Map Units:	US Survey Feet

Aerial photography

6" resolution color ortho photography

Appendix G: City of Norman

Background

The City of Norman project covers an area of approximately 256 square miles for orthophotography and 197 square miles for the planimetric and topographic update- see City of Norman Project Maps Appendix G Attachments A and B. The City of Norman contracted with Fugro, Inc in 2017 to update its orthophoto and planimetric data and Sanborn Map Company, Inc in 2015 to update topographic data.

Aerial photography

.25 and .5 foot resolution color orthophotography (2017 date)

Planimetrics (2017 Date)

See attachment C for features.

Topography (2015 Date)

1-foot elevation contours urban area 2-foot

Spot elevations

Hydrologically Re-enforced Digital Terrain Model (DTM) - breaklines and masspoints

LiDAR

Accuracy report

The City of Norman relies on a robust GIS to perform business operations. All data is stored in a 10.5.1 ArcSDE repository located in a MS SQL Server 2012 R2 database. At this time the City of Norman is seeking to upgrade to ArcSDE 10.6.1 and MS SQL Server 2012 R2 in the spring of 2019.

Respondents are directed to refer to the RFP, the following sections and the Data Dictionary, Appendix G Attachment C, section for technical specifications and a clear definition of the features and attributes that are considered deliverables, and therefore the responsibility of the Contractor to provide.

Objectives

The project has 3 objectives:

1. Obtain updated color digital orthophotos for 164 square miles at NMAAS 1" = 100' standards - 6 inch pixel resolution and 92 square miles at NMAAS 1" = 50' standards - 3 inch pixel resolution.
2. Update the city's planimetric mapping and for approximately 82 square miles at 1" = 50 and 115 square miles at 1" = 100' accuracy. See Data Dictionary Attachment C for features to be collected.
3. As an option - obtain 1 foot contours in the urban area and 2 foot contours for the rural portion of the project with raw LiDAR, classified bare earth points, Hydro flatten bare-earth DEM and DTM, Vertical Accuracy Report.

Scope of Work

The Contractor shall produce and deliver to the City of Norman photogrammetric change detection and update of the planimetric features to the standards stipulated in this section and elsewhere in this Request For Proposals. The Contractor shall furnish all materials, equipment, labor, management, insurance, postage, and transportation necessary to complete this work. The Respondent should propose the best procedures and commonly accepted professional techniques in order to assure complete compliance with this RFP.

All work required by the contract will be performed in conformance with these specifications and any contractual modifications to these specifications. Any deviation from the specifications, unless specifically authorized in writing by the GIS Project Manager, shall be sufficient cause for rejecting any part or all of the work performed.

Technical Specifications

The initial planimetric data and most recent aeriels followed the National Map Accuracy Standards (NMAS). It is expected that the deliverables from this contract shall have an overall average accuracy of 1 inch = 50 feet in urbanized areas and 1 inch = 100 feet. The respondent shall address the issue of the different accuracies of the other participating agencies as it relates to this project, and how they will maintain or improve the accuracy of the City of Norman's current datasets.

Planimetric Features

The planimetric data to be updated are road edges (paved, unpaved, trail centerlines, sidewalks and driveways), parking lots, buildings, (minimum size is 10' x 10'), hydrology (including drainage features such as ditches), railroad centerlines, street centerlines, tree mass outlines, single trees, fences, and utility points. At the request of our Engineering Division, we are adding several feature codes to existing layers to assisting in assessing stormwater applications. They are shaded in the data dictionary. All are new except for driveways, which they want separated into paved and unpaved. Sample digital data may be provided as an attachment. Respondents are also directed to refer to Appendix G - Attachment C of this RFP for a clear definition of the features and attributes that are considered deliverable, and therefore the responsibility of the Contractor to populate into the GIS database as part of the conversion effort. Respondents shall indicate in their technical plan of operations suggested data conversion techniques for the compilation of source map data.

Topographic Features

The topographic data to be collected must meet the most current Federal Emergency Management Agency's (FEMA) *Guidelines and Standards for Flood Risk Analysis and Mapping*. Respondents shall indicate in their technical plan of operations suggested data conversion techniques for the compilation of source map data.

Pilot Study For Planimetric and topographic data. The Pilot Study is necessary for the City of Norman to evaluate the process of detecting change and updating the planimetric data. The Pilot will be used to refine the scope of the remaining data conversion project in terms of quality, accuracy and, timeliness. An important component of this phase will be to clarify and test procedures used by the Contractor and the City to complete this project.

Selected Pilot Area The Pilot Study Area sections (Section 18 Township 9 North, Range 2 West for 1" = 50' and Section 29 Township 9 North, Range 1 West for 1" = 100') were chosen to be the pilots in this conversion process. The Pilot Study Area is a one square mile section in each scale.

Pilot Study Process In the City of Norman's conversion plan, the Contractor will be supplied with source data to use in the conversion process. The source material for this pilot will be a version of the planimetric feature dataset. The pilot study process will give the Contractor and the City of Norman the opportunity to work with the source data and

to identify and resolve any questions or problems that arise as actual data conversion is initiated. It gives both parties, prior to full production, the time needed to implement procedures and resolve problems reducing delays and reworks.

Scale and Accuracy of Planimetric Data

The final scale will be 1" = 50' and 1' = 100'. The respondent shall meet the National Map Accuracy Standard for such scale mapping. All spatial data shall conform to the following:

Coordinates/Projection:	State Plane Coordinate System,
Zone:	Oklahoma South, FIPS Zone 3502
Horizontal Datum:	HARN
Map Units:	Feet

Attribute Data

All required nongraphic attributes for the geodatabase are identified in Appendix G – Attachment C of this RFP. In the event that necessary attribute data is missing, confused, or unreadable on any source material, the Respondent will contact the City of Norman GIS Project Manager for assistance. In cases concerning minor irregularities in the data or source maps where the answer is obvious or defined by precedent, the Contractor may act to resolve the problem on his own initiative thereby reducing work stoppages and interruptions. When this occurs, the City of Norman GIS Project Manager shall be informed of the action that the Contractor took within 24 hours and the Contractor will document how the problem was resolved.

The City of Norman is seeking firm fixed prices for the performance and delivery of photogrammetric change detection and collection of the planimetric and topographic features. Prices shall cover all necessary work, materials, supplies, data preparation, entry, translation and quality control, etc. Reproduction, travel and other direct and indirect costs should also be included.

It is the responsibility of the Respondent to verify any count information used in estimating the cost of conversion. These estimates are based on the most current information available.

Deliverables

Cost Worksheet in Section 10 of the RFP must be completed.

Firm Fixed Unit Costs – Digital Color Orthoimagery (TIFF):

City of Norman: 92 miles @ 3" and 164 square miles @ 6"

Optional mosaic products:

MrSID of City of Norman

Photogrammetric products:

Planimetric Change Detection & Collection - Pilot Study Area Cost

Planimetric Change Detection & Collection - Remainder of the City -

82 square miles @ 1"=50' and 115 square miles @ 1"=100'

Features to be collected in Attachment C of this Appendix

Optional topographic products:

Geodatabase of topographic contours at 1' intervals the urban area (82 square miles) and 2' intervals in for the rural portion(115 square miles) of project area with spot elevations

- Breaklines


- Raw Lidar Point Cloud (LAS)

- Hydro flatten bare-earth DEM

- DTM


- FEMA compliant Vertical Accuracy Report (60 check points)

Attachment A - Orthophotography Project Map



City of Norman Project Map

Planimetric Coverage



Attachment C – Data Dictionary

TRANSPORTATION FEATURE DATASET

AIRPORT (Polygon)

Properties

Feature Dataset TRANSPORTATION Type: Polygon Topology/Network: n/a

Feature Class AIRPORT

Description

Visible airport runway related infrastructure within the imagery.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap
SHAPE	Geometry		Polygon			S	ArcMap
SHAPE_LENGTH	Double		<not null>			S	ArcMap
SHAPE_AREA	Double		<not null>			S	ArcMap
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor
CODE	Integer	4	0	Y		R	Conversion Vendor

Feature Subtype Domain Definitions

COD E	DESCRIPTIO N CLASS	Description
1812	Runway	Edge of paved surface
1813	Taxiway	Edge of paved surface
1814	Access Road	Edge of paved surface

ROAD (Polygon)

Properties

Feature Dataset TRANSPORTATION Type: Polygon Topology/Network: n/a

Feature Class ROAD

Description

Visible and hidden road and pavement-related features within the imagery.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap
SHAPE	Geometry		Polygon			S	ArcMap
SHAPE_LENGTH	Double		<not null>			S	ArcMap
SHAPE_AREA	Double		<not null>			S	ArcMap
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor
CODE	Integer	4	0	Y		R	Conversion Vendor

Feature Subtype Domain Definitions

COD E	DESCRIPTIO N CLASS	Description
1800	Paved Road	Paved road over 100' long, or 10' in width
1801	Paved Shoulder	Shoulder of road that is outside of the visible driving surface (paved road)
1802	Hidden Paved Road	Edge of paved road that is obscured by a bridge or other man-made feature. Collect to continue paved road surface
1803	Unpaved Road	Unpaved road over 100' long, or 10' in width. Unpaved surfaces will include dirt, gravel or other compact surface.
1804	Hidden Unpaved Road	Edge of unpaved road that is obscured by a bridge or other man-made feature. Collect to continue unpaved road surface
1805	Bridge Overpass	Pedestrian or vehicle bridge. Collect outer edge of bridge surface.
1806	Hidden Bridge Overpass	Pedestrian or vehicle bridge obscured by other bridge (interstate interchange is best example).
1807	Paved Alley	Paved alley over 50' long, or 8' in width.
1811	Curb	Edge of paved surface
1814	Road Under Construction	Collect as road under construction only if road is new or re-designed. If only a portion of road is under construction, collect as paved or unpaved surface.
1816	Unpaved Alley	Unpaved alley over 50' long, or 8' in width.
1825	Rural Trail	Unpaved paths on rural acreage.
1899	Median	Paved or unpaved median feature wholly contained within the road. Treat islands within roads as medians.

PARKING (Polygon)

Properties

Feature Dataset TRANSPORTATION Type: Polygon Topology/Network: n/a

Feature Class PARKING

Description

Paved or unpaved parking features visible within the imagery.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)
SHAPE	Geometry		Polygon			S	ArcMap	Internal geometry (assigned by ArcMap)
SHAPE_LENGTH	Double		<not null>			S	ArcMap	Internal attribute with calculated perimeter length of the polygon (assigned by ArcMap)
SHAPE_AREA	Double		<not null>			S	ArcMap	Internal attribute with calculated area of the polygon (assigned by ArcMap)
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a code identifying the feature. The description of the feature code is displayed.
CODE	Integer	4	0	Y		R	Conversion Vendor	Assigned by Conversion Vendor, this attribute identifies a general feature class code associated with each subtype. The description of the feature subtype is displayed.

Feature Subtype Domain Definitions

COD E	DESCRIPTIO N CLASS	Description
1809	Paved Parking	Commercial and/or Residential paved surfaces used primarily for parking vehicles. Must have at least 1 side that is 10' or greater to be compiled.
1816	Unpaved Parking	Commercial and/or Residential unpaved surfaces (dirt, gravel, grass, other) used primarily for parking vehicles. Must have at least 1 side that is 10' or greater to be compiled.
1822	Pervious Parking	Engineering code. Conversion vendor may see as paved.
1899	Island	Paved or unpaved island feature wholly contained within the parking feature. Treat medians within parking lots as islands.

UN-CLASSIFIED PAVEMENT (Polygon)

Properties

Feature Dataset TRANSPORTATION Type: Polygon Topology/Network: n/a

Feature Class PAVEMENT

Description

Pavement features visible within the imagery that are not contained in the ROAD or PARKING Feature Classes.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap
SHAPE	Geom		Polyg			S	ArcMap

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source
	entry		on				
SHAPE_LENGTH	Double		<not null>			S	ArcMap
SHAPE_AREA	Double		<not null>			S	ArcMap
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor
CODE	Integer	4	0	Y		R	Conversion Vendor

Feature Subtype Domain Definitions

CODE	DESCRIPTION CLASS	Description
1808	Paved Driveway	Paved commercial and/or residential driveway.
1823	Unpaved Driveway	
1810	Public Sidewalk	All public visible paved sidewalks, greater than 3'x10' in area, intended exclusively for pedestrian traffic.
1817	Private Sidewalk	All residential, commercial, or apartment complex paved sidewalks, greater than 3'x10' in area, intended exclusively for pedestrian traffic.
1820	Concrete Pad / Patio	Any miscellaneous concrete slabs such as concrete around swimming pool or a patio.

CO DE	DESCRIPTION CLASS	<i>Description</i>
1821	Deck / unpaved patio	Any gravel /bricked area or wood or composite decks

STRUCTURE FEATURE DATASET

BUILDING (Polygon)

Properties

Feature Dataset STRUCTURE Type: Polygon Topology/Network: n/a

Feature Class BUILDING

Description

Buildings and related structural elements visible in the imagery.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)
SHAPE	Geometry		Polygon			S	ArcMap	Internal geometry (assigned by ArcMap)
SHAPE_LENGTH	Double		<not null>			S	ArcMap	Internal attribute with calculated perimeter length of the polygon (assigned by ArcMap)
SHAPE_AREA	Double		<not null>			S	ArcMap	Internal attribute with calculated area of the polygon (assigned by ArcMap)
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a code identifying the feature. The description of the feature code is displayed.
CODE	Integer	4	0	Y		R	Conversion	Assigned by Conversion

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
	r						n Vendor	Vendor, this attribute identifies a general feature class code associated with each subtype. The description of the feature subtype is displayed.
BuildingHeight	Numeric					R	Conversion Vendor	Height of Building

Feature Subtype Domain Definitions

COD E	DESCRIPTIO N CLASS	Description
1700	Building	Polygon enclosing all erect (not under construction) buildings; i.e. houses, apartments, outbuildings, commercial. Building must have at least 1 side 10' or greater to be compiled.
1701	Approximate Building	Polygon enclosing buildings under construction. Building must have at least 1 side 10' or greater to be compiled.
1702	Foundation	Polygon enclosing all building foundations that do not contain a housing unit on top. Does not include buildings under construction but does include ruins.
1703	Single-wide Trailer	Polygon enclosing mobile home. Double-wide trailer shall be shown as building.
1799	Building Courtyard	Artificial polygon created when building is fully encompassing of an open area.

POOL (Polygon)

Properties

Feature Dataset STRUCTURE Type: Polygon Topology/Network: n/a

Feature Class POOL

Description

Swimming pools visible in the imagery.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
SHAPE	Geometry		Polygon			S	ArcMap	Internal geometry (assigned by ArcMap)
SHAPE_LENGTH	Double		<not null>			S	ArcMap	Internal attribute with calculated perimeter length of the polygon (assigned by ArcMap)
SHAPE_AREA	Double		<not null>			S	ArcMap	Internal attribute with calculated area of the polygon (assigned by ArcMap)
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a code identifying the feature. The description of the feature code is displayed.
CODE	Integer	4	0	Y		R	Conversion Vendor	Assigned by Conversion Vendor, this attribute identifies a general feature class code associated with each subtype. The description of the feature subtype is displayed.

Feature Subtype Domain Definitions

COD E	DESCRIPTIO N CLASS	Description
2003	Public Pool	Polygon enclosing all public swimming pools. Public pools will be evident by their size. Digitize the pool only, not the deck or paved area around the pool.

COD E	DESCRIPTIO N CLASS	Description
2004	Private Pool	Polygon enclosing all in-ground private swimming pools. Digitize the pool only, not the deck or paved area around the pool.

UN-CLASSIFIED STRUCTURES (Polygon)

Properties

Feature Dataset STRUCTURE Type: Polygon Topology/Network: n/a

Feature Class MISC_STRUCTURE

Description

Structures visible in the imagery that do not fit logically into the other Feature Classes under the STRUCTURE Feature Dataset.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)
SHAPE	Geometry		Polygon			S	ArcMap	Internal geometry (assigned by ArcMap)
SHAPE_LENGTH	Double		<not null>			S	ArcMap	Internal attribute with calculated perimeter length of the polygon (assigned by ArcMap)
SHAPE_AREA	Double		<not null>			S	ArcMap	Internal attribute with calculated area of the polygon (assigned by ArcMap)

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a code identifying the feature. The description of the feature code is displayed.
CODE	Integer	4	0	Y		R	Conversion Vendor	Assigned by Conversion Vendor, this attribute identifies a general feature class code associated with each subtype. The description of the feature subtype is displayed.

Feature Subtype Domain Definitions

COD E	DESCRIPTION CLASS	Level	Color	Weight	Style	Description
1709	Dam	41	0	2	2	Barrier across river, creek, or swamp to regulate or obstruct water flow. Visible beaver dams large enough to affect water flow shall be outlined also.
1710	Oil Storage Tank	17	1	1	0	Polygon enclosing oil storage tank.
1711	Signal Controller	35	5	1	0	Square or rectangular metal box found in right of way at intersection used to control overhead traffic signal.
1712	Well House					
1713	Substation					
1714	Cell Phone Tower					
1715	Other Oil/Gas					

COD E	DESCRIPTIO N CLASS	Lev el	Color	Weig ht	Style	Description
	Facility					

BARRIER (Line)

Properties

Feature Dataset STRUCTURE Type: Line Topology/Network: n/a

Feature Class BARRIER

Description

This feature class includes all man-made barriers such as walls and/or fences.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)
SHAPE	Geometry		Line			S	ArcMap	Internal geometry (assigned by ArcMap)
SHAPE_LENGTH	Double		<not null>			S	ArcMap	Internal attribute with calculated length of the Line (assigned by ArcMap)
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a code identifying the feature. The description of the feature code is displayed.
CODE	Integer	4	0	Y		R	Conversion Vendor	Assigned by Conversion Vendor, this attribute identifies a general feature

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
								class code associated with each subtype. The description of the feature subtype is displayed.

Feature Subtype Domain Definitions

COD E	DESCRIPTIO N CLASS	Description
1704	Wall	Line showing fixed structure of concrete or brick not used for retention of earth
1705	Head Wall	Concrete on the end of a transverse drain or pipe culvert.
1706	Fence	Commercial or residential fence meant to show distinction between adjacent properties.
1707	Retaining Wall	Fixed structure retaining earth. Structure can be concrete or other man-made surface.

LAND USE FEATURE DATASET

LAND USE (Polygon)

Properties

Feature Dataset LAND USE Type: Polygon Topology/Network: n/a
Feature Class LAND USE

Description

Features relating to land use that are visible in the imagery.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)
SHAPE	Geometry		Polygon			S	ArcMap	Internal geometry (assigned by ArcMap)
SHAPE_LENGTH	Double		<not null>			S	ArcMap	Internal attribute with calculated perimeter length of the polygon (assigned by ArcMap)
SHAPE_AREA	Double		<not null>			S	ArcMap	Internal attribute with calculated area of the polygon (assigned by ArcMap)
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a code identifying the feature. The description of the feature code is displayed.
CODE	Integer	4	0	Y		R	Conversion Vendor	Assigned by Conversion Vendor, this attribute identifies a general feature class code associated with each subtype. The description of the feature subtype is displayed.

Feature Subtype Domain Definitions

COD E	DESCRIPTIO N CLASS	Level	Color	Weight	Style	Description
-------	--------------------	-------	-------	--------	-------	-------------

COD E	DESCRIPTIO N CLASS	<i>Lev el</i>	<i>Color</i>	<i>Weig ht</i>	<i>Style</i>	<i>Description</i>
1500	Wooded Area	50	2	1	0	Polygon indicating a tree line or edge of a forest
1501	Cemetery	25	3	1	5	Approximate polygon boundary enclosing a cemetery. If cemetery is bound by fence or wall, that feature shall have precedence over cemetery.
1502	Quarry / Borrow Pit	28	2	1	2	Mining area. No distinction is made between rock (consolidated) material mines and loose (unconsolidated) material mines.

TREE (Point)

Properties

Feature Dataset LAND USE Type: Point Topology/Network: n/a

Feature Class TREE

Description

Points showing individual street trees.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)
SHAPE	Geometry		Point			S	ArcMap	Internal geometry (assigned by ArcMap)
SYMBOL	Integer		0	Y		S	ArcMap/Conversion Vendor	Internal attribute storing the symbol of the point feature (used by ArcMap)
ANGLE	Integer		0			S	ArcMap/Conversion	Internal attribute storing the rotation angle for the symbol

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
							n Vendor	(used by ArcMap)
FEATURE_SUBTYPE	Text	30	1	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a code identifying the feature. The description of the feature code is displayed.
CODE	Integer	4	0	Y		R	Conversion Vendor	Assigned by Conversion Vendor, this attribute identifies a general feature class code associated with each subtype. The description of the feature subtype is displayed.

Feature Subtype Domain Definitions

COD E	DESCRIPTION CLASS	Description
1503	Tree	Point showing single tree (on public or private property) that has a canopy diameter of at least 20' – do not show small ornamental trees or shrubs.

HYDROLOGY FEATURE DATASET

HYDROLOGY_WATERBODY (Polygon)

Properties

Feature Dataset HYDROLOGY Type: Polygon

Topology/Network: Topology

Feature Class HYDROLOGY_WATERBODY

Description

Visible double line hydrology and standing water bodies within the imagery.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)
SHAPE	Geometry		Polygon			S	ArcMap	Internal geometry (assigned by ArcMap)
SHAPE_LENGTH	Double		<not null>			S	ArcMap	Internal attribute with calculated perimeter length of the polygon (assigned by ArcMap)
SHAPE_AREA	Double		<not null>			S	ArcMap	Internal attribute with calculated area of the polygon (assigned by ArcMap)
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a code identifying the feature. The description of the feature code is displayed.
PK_COM_ID	Long Integer		<not null>		PK	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a unique common identifier assigned to each hydro shape feature to support NHD modeling.
CODE	Integer	4	0	Y		R	Conversion Vendor	Assigned by Conversion Vendor, this attribute identifies a general feature

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
								class code associated with each subtype. The description of the feature subtype is displayed.
NAME	Text	50	<null>			O		Common/Local Name for water body. Not intended for GNIS compatibility.

Feature Subtype Domain Definitions

COD E	DESCRIPTION CLASS	Description
1602	River / Stream	Well-defined shoreline of streams and rivers with an average width greater than 10' wide.
1603	Approximate River / Stream	Approximate shoreline of streams and rivers with an average width greater than 10' wide. River / Stream takes precedence over this feature. Entire feature must have undefined or approximate shoreline to qualify.
1604	Lake	Shoreline of natural lake. Determination of actual feature type is subjective and assigned by Conversion Vendor staff.
1605	Farm Pond	Shoreline of non-industrial pond not found in a residential or commercial development. Determination of actual feature type is subjective and assigned by Conversion Vendor staff.
1606	Industrial Pond	Shoreline of industrial pond used for treating industrial or man-made refuse. Determination of actual feature type is subjective and assigned by Conversion Vendor staff.
1607	Reservoir	Shoreline of man-made reservoir. Reservoir will be defined as a water body containing an Earthen dam or man-made damn feature on one end of the water body. Determination of actual feature type is subjective and assigned by Conversion Vendor

COD E	DESCRIPTIO N CLASS	<i>Description</i>
		staff.
1610	Hidden River / Stream	Shoreline of stream or river with an average width greater than 10' wide obscured by an overhead feature.
1611	Natural Channel	
1699	Island	Shoreline of feature and collected <i>only</i> if necessary to produce contiguous features (i.e. clarification of a void area).
2400	Detention Pond	Shoreline of non-industrial pond found in a residential or commercial development. Determination of actual feature type is subjective and assigned by Conversion Vendor staff.
2401	Retention Pond	
2402	Paved Channel	Paved ditch or channel designed to constrict the flow of water.
2403	Pipe / Culvert	Large culverts or above-ground pipes that tie into the hydrographic network. Determination of actual feature type is subjective and assigned by Conversion Vendor staff.

HYDROLOGY DRAIN (Line)

Properties

Feature Dataset HYDROLOGY Type: Line Topology/Network: Topology

Feature Class HYDROLOGY_DRAIN

Description

The visible centerline of a hydrology feature within the imagery that is less than 10' wide. Additionally, centerline abstractions oriented in the direction of flow through all open water bodies captured in the hydrology_waterbody feature class. The resulting lines are designed to create a geographic network compatible with the National Hydrological Dataset (NHD) modeling standards for representing NHD drainage network.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)
SHAPE	Geometry		Line			S	ArcMap	Internal geometry (assigned by ArcMap)
SHAPE_LENGTH	Double		<not null>			S	ArcMap	Internal attribute with calculated length of the Line (assigned by ArcMap)
FEATURE_SUBTYPE	Text	30	0	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a subtype identifying the feature. The description of the feature subtype is displayed.
NHD_FTYPE	Text	24	<null>	Y		O	NHD	Type of NHD network element. NHD feature types include: Artificial Path, Canal/Ditch (1-dimensional), Connector, Pipeline, and Stream/River (1-dimensional)
NHD_FCODE	Integer	5	<null>			O	NHD	Numeric value that encodes the type and values for a set of characteristics for an NHD feature. This five-digit code has two parts: the first three digits encode the feature type; the last two digits encode values for a set of characteristics associated with the feature.

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
PK_COM_ID	Long Integer	10	<not null>		PK	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a unique identifier of each hydrology drain element in the network to support NHD modeling.
CODE	Integer	4	0	Y		R	Conversion Vendor	Assigned by Conversion Vendor, this attribute identifies a general feature class code associated with each subtype. The description of the feature subtype is displayed.
NAME	Text	50	<null>			O		Common/Local Name for drain feature. Not intended for GNIS compatibility.
FK_WB_COM_ID	Long Integer	10	-9999		FK	R	NHD	Unique identifier of the waterbody that the network element (artificial path only) flows through. (-9999 FOR Not Applicable)
FK_NHD_RCH_CO M_ID	Long Integer	10	<null>		FK	O	NHD	Unique identifier of the transport reach and coastline reach of which the network element is part. (Tie to NHD)

Feature Subtype Definitions (Domain)

COD E	DESCRIPTIO N CLASS (NHD _FTYPE)	<i>Description</i>
1600	Single Line Stream	Centerline of creek or stream with an average width LESS than 10' wide.
1601	Hidden Single Line Stream	Centerline of creek or stream with an average width LESS than 10' wide obstructed by an overhead feature.
1602	River / Stream	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
1603	Approximate River / Stream	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
1604	Lake	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
1605	Farm Pond	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
1606	Industrial Pond	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
1607	Reservoir	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
1610	Hidden River / Stream	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
1611	Natural Channel	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
2400	Detention Pond	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
2401	Retention Pond	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
2402	Paved Channel	A centerline abstraction to facilitate hydrologic modeling through open water bodies.
2403	Pipe / Culvert	A centerline abstraction to facilitate hydrologic modeling through open water bodies.

HYDROLOGY POINT SOURCE (Point)

Properties

Feature Dataset HYDROLOGY Type: Line Topology/Network: n/a

Feature Class HYDROLOGY_POINT_SOURCE

Description

Single points showing source of input into the hydrographic model.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)
SHAPE	Geometry		Point			S	ArcMap	Internal geometry (assigned by ArcMap)
SYMBOL	Integer		0	Y		S	ArcMap/Conversion Vendor	Internal attribute storing the symbol of the point feature (used by ArcMap)
ANGLE	Integer		0			S	ArcMap/Conversion Vendor	Internal attribute storing the rotation angle for the symbol (used by ArcMap)
FEATURE_SUBTYPE	Text	30	1	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a code identifying the feature. The description of the feature code is displayed.
CODE	Integer	4	0	Y		R	Conversion Vendor	Assigned by Conversion Vendor, this attribute identifies a general feature class code associated with

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
								each subtype. The description of the feature subtype is displayed.

Feature Subtype Domain Definitions

COD E	DESCRIPTION CLASS	Description
2404	Storm Inlet	Catch basin or inlet located within a curb, road or parking feature.

UTILITY FEATURE DATASET UTILITY POINT (Point)

Properties

Feature Dataset UTILITY Type: Point Topology/Network: n/a

Feature Class UTILITY_POINT

Description

Single point features showing location of visible utility features.

Attributes

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
--------------	------	--------	---------------	--------	-------	----------------------------	-------------	-------------

Name (Alias)	Type	Length	Default Value	Domain	Index	System, Required, Optional	Data Source	Description
OBJECTID (FID)	Object ID		<not null>		Y	S	ArcMap	Internal object / feature ID number (assigned by ArcMap)
SHAPE	Geometry		Point			S	ArcMap	Internal geometry (assigned by ArcMap)
SYMBOL	Integer		0	Y		S	ArcMap/ Conversion Vendor	Internal attribute storing the symbol of the point feature (used by ArcMap)
ANGLE	Integer		0			S	ArcMap/ Conversion Vendor	Internal attribute storing the rotation angle for the symbol (used by ArcMap)
FEATURE_SUBTYPE	Text	30	1	Y	Y	R	Conversion Vendor	Assigned by Conversion Vendor, this attribute is a code identifying the feature. The description of the feature code is displayed.
CODE	Integer	4	0	Y		R	Conversion Vendor	Assigned by Conversion Vendor, this attribute identifies a general feature class code associated with each subtype. The description of the feature subtype is displayed.

Feature Subtype Domain Definitions

COD E	DESCRIPTIO N CLASS	Description
1901	Utility Pole	Point indicating a single feature.
1902	Street Light	Point indicating a single feature

[Appendix H: Canadian County \(ACOG\)](#)

Background

The County of Canadian County has a population of 718,633. The County encompasses 720 square miles. The last Orthos were flown in 2010.

Projection

All spatial data shall conform to the following projection:

Coordinates/Projection:	NAD 1983 StatePlane,
Zone:	Oklahoma North FIPS 3501 Feet
Horizontal Datum:	NAD 83
Map Units:	Feet

Aerial Photography

6" OR 12" Resolution color ortho photography

Deliverables

Cost Worksheet in Section 10 of the RFP must be completed.

The final ortho deliverables will be required to be in:

GeoTIFF, uncompressed

MrSID, compressed no greater than 15:1*

*Note: No re-compression of compressed data is acceptable. Image mosaics shall be equal in quality to image tiles.

[Appendix I: Forms](#)

All forms in this section must be submitted with the proposal.

All forms associated with this RFP are to be delivered to **(ACOG) Association of Central Oklahoma Governments, 4205 N. Lincoln Blvd., Oklahoma City, OK, 73105**. ACOG will distribute the Proposals to the members of COAGA 2019.

1. Non-collusion Affidavit – City of Edmond
2. Non-collusion Affidavit – City of Del City
3. Non-collusion Affidavit – City of Midwest City
4. Non-collusion Affidavit – City of Moore
5. Non-collusion Affidavit – City of Norman
6. Non-collusion Affidavit – Canadian County (ACOG)
7. Non-collusion Affidavit – General

Appendix J: Metadata Requirements

Metadata shall be produced in a format (FGDC CSDGM (TXT) or FGDC CSDGM) that can be imported into the Metadata Editor in ArcCatalog. At minimum, metadata shall include the following information:

Identification_Information:

Citation:

Citation_Information:

Originator:

Publication_Date:

Title:

Geospatial_Data_Presentation_Form:

Online_Linkage:

Description:

Abstract:

Purpose:

Time_Period_of_Content:

Time_Period_Information:

Single_Date/Time:

Calendar_Date:

Currentness_Reference:

Status:

Progress:

Maintenance_and_Update_Frequency:

Spatial_Domain:

Bounding_Coordinates:

West_Bounding_Coordinate:

East_Bounding_Coordinate:

North_Bounding_Coordinate:

South_Bounding_Coordinate:

Keywords:

Theme:

Place:

Access_Constraints:

Use_Constraints:

Native_Data_Set_Environment:

Data Quality:

Positional Accuracy:

Horizontal Accuracy:

Spatial_Reference_Information:

Horizontal_Coordinate_System_Definition:

Planar:

Grid_Coordinate_System:

Grid_Coordinate_System_Name:

State_Plane_Coordinate_System:

SPCS_Zone_Identifier:

Lambert_Conformal_Conic:

Standard_Parallel:

Standard_Parallel:

Longitude_of_Central_Meridian:

Latitude_of_Projection_Origin:

False_Easting:

False_Northing:

Planar_Coordinate_Information:

Planar_Coordinate_Encoding_Method:

Coordinate_Representation:

Abscissa_Resolution:

Ordinate_Resolution:

Planar_Distance_Units:

Geodetic_Model:

Horizontal_Datum_Name:

Ellipsoid_Name:

Semi-major_Axis:

Denominator_of_Flattening_Ratio:

Entity Attribute:

Detailed Description:

Entity Type:

Label:

Definition:

Definition Source:

Attribute:

Definition:

Definition Source:

Distribution_Information:

Distributor:

Contact_Information:

Contact_Organization_Primary:

Contact_Organization:

Contact_Person:

Contact_Position:

Contact_Address:

Address_Type:

Address:

State_or_Province:

Postal_Code:

Contact_Voice_Telephone:

Contact_Facsimile_Telephone:

Contact_Electronic_Mail_Address:

Hours_of_Service:

Distribution_Liability:

Data_Quality_Information:
Attribute_Accuracy:
Attribute_Accuracy_Report:
Logical_Consistency_Report:
Completeness_Report:
Positional_Accuracy:
Horizontal_Positional_Accuracy:
Horizontal_Positional_Accuracy_Report:

Lineage:
Source_Information:
Source_Citation:
Citation_Information:
Originator:
Publication_Date:
Title:
Geospatial_Data_Presentation_Form:
Source_Scale_Denominator:
Type_of_Source_Media:
Source_Time_Period_of_Content:
Time_Period_Information:
Range_of_Dates/Times:
Beginning_Date:
Ending_Date:
Source_Currentness_Reference:
Source_Citation_Abbreviation:
Source_Contribution:

Process_Step:
Process_Date:
Process_Description:
Process_Contact:
Contact_Information:
Contact_Person_Primary:
Contact_Person:
Contact_Organization:
Contact_Address:
Address_Type:
Address:
City:
State_or_Province:
Postal_Code:
Country:
Contact_Voice_Telephone:
Contact_Facsimile_Telephone:
Contact_Electronic_Mail_Address:
Hours_of_Service:
Cloud_Cover:

Metadata_Reference_Information:

Metadata_Date:
Metadata_Review_Date:
Metadata_Contact:
 Contact_Information:
 Contact_Organization_Primary:
 Contact_Organization:
 Contact_Person:
 Contact_Address:
 Address_Type:
 Address:
 City:
 State_or_Province:
 Postal_Code:
 Contact_Voice_Telephone:
 Contact_Facsimile_Telephone:
 Contact_Electronic_Mail_Address:
 Hours_of_Service:
Metadata_Standard_Name:
Metadata_Standard_Version:
Metadata_Use_Constraints: